





# STORMWATER UTILITY FEASIBILITY STUDY

Centreville Town Council  
101 Lawyers Row  
Centreville, Maryland 21617



October 18, 2010



5400 Limestone Road  
Wilmington, DE 19808



4051 Ogletown Road  
Newark, DE 19713

Financial assistance provided by the Coastal Zone Management Act of 1972, as amended, administered by the Office of Ocean and Coastal Resource Management, National Oceanic and Atmospheric Administration.

## TABLE OF CONTENTS

|  | <b><u>Pages</u></b> |
|--|---------------------|
| Executive Summary  | i - ii              |
| Section One. Introduction and Background                                       | 1 - 3               |
| Section Two. Current Functions and Expenditures                                | 6 - 8               |
| Section Three. Existing Program and Projected Future Expenditures              | 9                   |
| Section Four. Revenue Collection Framework                                     | 10 - 12             |
| Section Five. Recommendations  | 14 - 17             |
| Appendices   |                     |
| A    Estimates of Expenditures   |                     |
| B    Revenue Collection Framework  |                     |
| Attachment   |                     |
| 1    Inlet Inspection Reports<br>Pond Reports<br>Infiltration Facility Reports |                     |
| 2    Photographs   |                     |

## EXECUTIVE SUMMARY

The objectives of this study were to assess the condition of the existing storm drainage infrastructure and stormwater management facilities, generally determine future needs, and evaluate the issues associated with creating a stormwater utility for the Town of Centreville. The study was geared toward providing a framework for utility development and establishing general feasibility. Resolving the numerous intricacies and actual implementation of a utility were not included and would need to be provided in a subsequent phase. Funding for the study was provided by Maryland Department of Natural Resources (DNR) through the Chesapeake & Coastal Program (CCP), Coastal Programs Initiative (CCI). Components of the study included field reconnaissance, GIS analyses, defining the existing program and identifying potential enhancements, developing a revenue collection framework, and preparing a final report.

The Town is generally responsible for the inspection, maintenance, rehabilitation, and construction of the storm drainage system within the Town limits comprising approximately 700 inlets and an unknown number of miles of storm sewer. Town Public Works uses a trailer-mounted Vac-tron and a Sweeper truck. Several issues are known to exist. For example, the Town is currently repairing a storm sewer located adjacent to a sludge drying bed at the Town's wastewater treatment plant that is badly eroded at the outfall. There are also plans to construct another two or three retrofit projects in the next 12 months using State 319 Funds and 2011 Trust Funds. The on-going maintenance of the existing stormwater retrofit projects, in addition to the proposed projects, will be the responsibility of the Town personnel.

Expenditures coinciding with the Existing Program were summarized into spreadsheet format and were projected out five years using an escalation factor of 2.5 percent to present more than just a "snapshot" of needs and approaches. Projected future costs coinciding with program improvements were derived by interviews with Town personnel, field work performed by URS, and review of provided documents. Three potential levels of service (LOS) were evaluated and are detailed in the spreadsheet in Appendix A:

**Level of Service One or "Essential"** includes the Existing Program as well as hardware and software costs that would be incurred should a stormwater utility be implemented, replacement of the Vac-tron and the street sweeper, payments into a capital recovery fund or bond payments to enable major capital projects to be undertaken, maintenance of retrofit projects previously undertaken by the Town, and preparation of a more detailed inventory of the drainage infrastructure (inlets, pipes, and outfalls).

**Level of Service Two or "Enhanced"** includes Level of Service One expenditures plus projects that begin moving the Town toward a more proactive approach to managing stormwater such as construction and subsequent maintenance of low impact stormwater management facilities as recommended in the LID Restoration Master Plan, compliance with TMDLs, and additional staff time.

**Level of Service Three or "Optimal"** includes Level of Service Two expenditures but more aggressively advances the proactive approach including a higher level of treatment per the LID Master Plan, maintenance of stormwater management basins and payments into a capital recovery fund or bond payments to enable retrofits should the Town decide to assume responsibility for basins currently privately-owned, compliance with the NPDES MS4 permit program, and additional staff time.

The impervious coverage associated with five land uses in Centreville (single family residential, multi-family residential, commercial/industrial, public/institutional, and roads) was estimated through GIS evaluations. These evaluations indicated that the amount of impervious surface for the average single-family detached residential property in Centreville is approximately 3,200 square feet. Therefore, this figure is used as the Equivalent Residential Unit (ERU). ERUs provide a common measure to compare residential and nonresidential properties. The number of ERUs for each of the land uses was determined by simply dividing the total calculated impervious coverage by the ERU figure of 3,200 square feet.

A framework for deriving revenues under this concept was developed and provided in Appendix B. Example Unit Rates show how much revenue would be collected from each land use category with an ERU rate of \$1.00. These unit values were extrapolated for other ERU rates (not shown) such that rates corresponding to each level of service could be estimated. Alternatives to this type of ERU approach exist including determining the impervious amount of cover on each and every residential parcel or for each residential zoning district. The framework spreadsheet is based on numerous assumptions and the rates shown are for example only and should not be used for any type of budgeting projection.

Since stormwater management practices employed on some properties may result in a lesser runoff contribution to the drainage system, various credit programs have been developed. For this study, a credit for the approximate 660 residential properties draining to a privately-maintained detention or retention basin was assumed. Also, placeholders for two commercial/industrial credits were included. This assessment assumed that tax-exempt properties in Centreville would contribute to a stormwater utility in the same way that every other property would. (State and County buildings, while exempt from Town property tax, pay water and sewer fees based on usage.) The exception to this would be State and Town roadways which were assumed to be exempted.

One of the most difficult issues regarding surface water management in Maryland and throughout the country is the reliance on private entities for the maintenance of stormwater management structures. Assumption of maintenance responsibilities by the Town would be advantageous for a number of reasons. HOA officers would be relieved from the burden of maintaining their community's basins, total expenditures would be reduced if a single agency performed the maintenance work and/or oversaw contractors due to economies of scale, and water quality in the Town would be improved through enhanced maintenance. However, the costs associated with annual maintenance as well as the inevitable retrofits could significantly increase revenues needed to run the stormwater program. In the end, any such policy change would need to be fully vetted in the public arena with advantages and disadvantages fully explored.

The final phase of utility implementation would necessitate two broad actions by the Town to effectively resolve the issues described in these recommendations:

**Create a Citizens Advisory Committee** – The Committee, comprised of a diverse group of stakeholders, would better define the program and assure that it matches residents' and merchants' expectations and willingness-to-pay. The Committee could also hold public forums on utility development. A clear mission with overall time frame would be needed from the Town to assure the group stays focused.

**Prepare a Business Plan** – A utility cannot be created without a solid foundation. A Business Plan which would build upon, but better detail and fine tune, the expenditure and revenue estimates presented herein is essential. The Plan would also address various implementation details and resolve policy issues.

Some jurisdictions have conducted similar assessments only to decide that a utility is not appropriate for them at the current time or under existing conditions. In other words, there is nothing improper with evaluating the potential for utility development and then deciding to not pursue it further. However, proceeding without necessary due diligence and understanding of residents' expectations and then failing in the implementation could be very problematic.

This report was prepared by URS Corporation and Duffield Associates under award number NA09NOS4190170 from the Office of Ocean and Coastal Resource Management (OCRM), National Oceanic and Atmospheric Administration (NOAA), through the Maryland Department of Natural Resources Chesapeake and Coastal Program. The statements, findings, conclusions and recommendations are those of the author(s) and do not necessarily reflect the views of NOAA or the U.S. Department of Commerce.

## **SECTION ONE. INTRODUCTION AND BACKGROUND**

In February 2010, the Town of Centreville retained the services of URS Corporation to perform a Stormwater Utility Feasibility Study. Due to a change in personnel, URS subcontracted a portion of the work to Duffield Associates, Inc. The objectives of the study were to assess the condition of the existing storm drainage infrastructure and stormwater management facilities, generally determine future needs, and evaluate the issues associated with creating a stormwater utility for the Town. The study was geared toward providing a framework for utility development and establishing general feasibility. Resolving the numerous intricacies and actual implementation of a utility were not included and would need to be provided in a subsequent phase. Funding for the study was provided by Maryland Department of Natural Resources (DNR) through the Chesapeake & Coastal Program (CCP), Coastal Programs Initiative (CCI).

A stormwater utility would function similarly to a potable water or electric utility where revenues and expenditures associated with stormwater conveyance and management would be accounted for on an individual property basis and separately from other Town functions. Under the utility concept, businesses and residents are assessed a fee that is based on the amount of stormwater runoff produced by their property which in turn is a function of the amount of impervious surfaces such as roof tops and paving that are present on each site. Whereas usage of other utilities like water and electric can typically be quantified with a meter or similar device, rates of runoff cannot be measured as easily and therefore imperviousness is commonly relied upon as an approximation of the amount a user is contributing to the drainage system.

The number of stormwater utilities in the United States is growing each year. It has been estimated that there are currently about 1,000 nationwide. They vary significantly throughout the country and must be tailored to meet local needs and conditions but in general, involve restructuring existing municipal operations, developing a comprehensive stormwater program, and providing adequate, stable, and equitable funding for the program.

Stormwater utilities operate under the premise that those who contribute more runoff to the drainage infrastructure pay more for constructing and maintaining the system. Therefore, this is considered an equitable method of allocating costs. Centreville currently uses its general revenues, principally derived from property taxes, for its stormwater-related expenditures. In instances where larger, mostly impervious parcels are assessed a higher value than smaller or less developed parcels, equity may already exist. However, if there are cases when smaller lots with less impervious surfaces are assessed a higher value than larger, mostly developed lots, the current funding mechanism could be considered inequitable.

The Town's decision to analyze utility feasibility is timely. Throughout the State and across the country, concerns regarding stormwater management and conveyance are evolving from mostly an individual matter related to flooding concerns to one of more of a community level related to water quality. Regulatory programs such as Total Maximum Daily Loads (TMDLs) and the National Pollutant Discharge Elimination System (NPDES) municipal separate storm sewer system (MS4) permits are resulting in cities and counties evaluating methods by which surface water management programs can be funded.

It should be noted that the Chesapeake Bay TMDL's will be finalized in December 2010 and the Maryland Phase 1 Watershed Implementation Plan (WIP) is currently in a public review period. The Phase II WIP, which is scheduled to be adopted by November 2011, will add specificity to the Phase I WIP and could likely include additional requirements for non-point runoff.

If Centreville decides to implement a stormwater utility, it would most likely be one of the smaller cities in the country, from a population standpoint, to do so. Lewes, Delaware (population 3,200) recently enacted a stormwater “tariff” which is essentially a utility fee. Research found similar programs in cities as small as Bluffton, South Carolina (population 4,100); and Lancaster (population 4,070) and Vernon (population 7,230), both in Wisconsin. This is important as there are certain fixed costs associated with a utility and since Centreville is smaller than most cities that have adopted this approach, the lack of economies of scale could result in higher than average rates.

The scope of work for this Stormwater Utility Feasibility Study was as follows:

### **Field Reconnaissance**

As part of the overall feasibility assessment, URS conducted a field inventory and assessment of stormwater infrastructure located within the Town limits. Field work was divided into two separate tasks as described below.

#### *Best Management Practices (BMPs)*

An inventory provided by the Queen Anne’s County Department of Public Works (QACDPW) was used to identify the locations of BMPs throughout the Town. BMPs included wet ponds and dry ponds (33), infiltration practices (8), and sand filters (2) for a total of 43 structures. Each facility was surveyed using sub-meter accurate GPS equipment. The survey included the perimeter of the BMP, entry and discharge points as well as the location of any defects. The condition of each BMP was assessed and a series of digital photographs was collected to document the inspection and condition of the BMP. A representative from the QACDPW was present for some of the inspections.

In addition to the BMP’s noted above, the Town has also recently constructed several stormwater retrofit projects including the Coastal Plain Outfall near Banjo Lane, the Wooded Wetland near the entrance to the Town’s wastewater treatment plant and a Bioswale at the Police Station. Funds will need to be budgeted annually for the on-going maintenance of these facilities. The undertaking of additional retrofit projects as recommended in the LID Restoration Master Plan prepared by EcoSite, Inc. will exacerbate this funding situation.

#### *Drainage Inlets*

Each drainage inlet (i.e. catch basin) in the Town was located and surveyed using sub-meter accurate GPS equipment. A total of 687 drainage inlets were located, with approximately two thirds located in the Northbrook and Symphony Village developments. Following the GPS survey, the condition of a representative sample of the inlets (57 total) was assessed. Emphasis was placed on older inlets located in the center of the Town, with a smaller sampling of inlets from Northbrook and Symphony Village also included. Inlet walls, frames, grates and pipe connections were assessed and the presence of collected sediment and / or debris was noted. In addition, each of the sample inlets was opened and photographed.

In general, it was found that the storm drainage system in Centreville is in reasonable condition and other than minor maintenance such as removal of obstructions, no further work appeared to be needed in the near-term. However, as noted in Section Two, there may be some capacity issues the Town may need to address.

The location of the facilities described above can be found in Figures 1 and 2.

## **GIS Analyses**

GIS information obtained from the County was used for the purposes of calculating impervious surface coverages for various land uses. This analysis is further described in Section Four.

## **Defining Existing Program and Identifying Potential Enhancements**

Current efforts were determined mostly through interviews with appropriate Town personnel. Potential enhancements were also discussed during the interviews but were also identified by field work and review of documents provided by the Town. Costs associated with program improvements were estimated based on collective asset management experiences coupled with various distributed guidelines. Three potential levels of service were identified as described in Section Three.

## **Developing Revenue Collection Framework**

Utilizing existing GIS data, the approximate amount of impervious cover corresponding to a variety of existing land uses was estimated. Impervious coverage of public roadways was included as these are often exempted from a utility fee. The equivalent residential unit (ERU), as defined in Section Four, was calculated and a framework for calculating corresponding square footage fees matching three potential levels of service was developed. Finally, subdivisions with their own stormwater management basins were identified as these may qualify for a credit.

## **Final Report and Recommendations**

This report concludes the feasibility study and completes Phase I of the CCP, CCI grant. This assessment was based on very approximate expenditure estimates and restrictive GIS data. In-depth evaluations were not possible and also outside the scope of this evaluation. While a framework for potential fees is offered, this report is intended more to provide the Town with the tasks and policy decisions that would be needed should it decide to proceed with the second and final phase of utility implementation.

This report was prepared by URS Corporation and Duffield Associates under award number NA09NOS4190170 from the Office of Ocean and Coastal Resource Management (OCRM), National Oceanic and Atmospheric Administration (NOAA), through the Maryland Department of Natural Resources Chesapeake and Coastal Program. The statements, findings, conclusions and recommendations are those of the author(s) and do not necessarily reflect the views of NOAA or the U.S. Department of Commerce.

Figure 1



Figure 2

## **SECTION TWO. CURRENT FUNCTIONS AND EXPENDITURES**

### **General Function and Responsibilities**

The Town of Centreville is generally responsible for the inspection, maintenance, rehabilitation, and construction of the storm drainage system within the Town limits comprising approximately 700 inlets and an unknown number of miles of storm sewer. Though the Maryland State Highway Administration has maintenance responsibility for the drainage systems within State rights-of-way, the Town will often perform tasks at these locations such as removing debris from grates. Town employees mow and occasionally perform rudimentary work on open channels. Review of the stormwater management and erosion and sediment control portions of development plans, as well as inspections during construction, is handled by Queen Anne's County.

Town Public Works staff is proactive with their maintenance program by routinely inspecting and cleaning inlets particularly before major rain events. They use a trailer-mounted Vac-tron to vacuum sediment from inlets and clear debris from pipes with an attached jet washer. These tasks are usually performed annually in the center of Town and on an as-needed basis elsewhere. The Vac-tron equipment is used on an approximate half time basis for stormwater-related tasks, and is occasionally used by the Water Department as well. The Town also has a Sweeper truck which is used daily in the center of Town as well as weekly on pre-assigned routes in other areas.

Construction, when needed, is handled either by Town crews for smaller projects or under contract for larger projects. Several issues are known to exist. For example, the Town is currently repairing a storm sewer located adjacent to a sludge drying bed at the Town's wastewater treatment plant that is badly eroded at the outfall. There are also plans to construct another two or three retrofit projects in the next 12 months using State 319 Funds and 2011 Trust Funds. As mentioned earlier, the ongoing maintenance of the existing stormwater retrofit projects in addition to the proposed projects will be the responsibility of the Town personnel.

### **Expenditures**

The Vac-tron was estimated by staff to cost approximately \$30,000. It requires a two person crew to operate and if used on a half-time basis, this equates to one full-time equivalent (FTE) position. Another FTE is needed for the Sweeper truck. Mowing of open channels necessitates a two person crew but at an estimated one quarter time. Miscellaneous maintenance work also necessitates a two person crew at an estimated one quarter time. Collectively, these tasks result in one FTE. The Public Works Superintendent spends approximately one quarter time on stormwater-related issues as does the Watershed Manager.

Current staffing is considered adequate but not excessive. Enhancing the stormwater program or assuming additional responsibilities as described below could result in the need for additional employees. Also, the Sweeper vehicle is approximately 10 years old and will need to be replaced in the not too distant future.

### **Needs and Priorities**

Ponding in roads often occurs after heavy rains which can create nuisance issues of splashing water as well as safety concerns when ponded water freezes in the winter. In addition to obvious safety concerns, ponding water on roadways can also cause deterioration of paving, base courses and subgrade.

Conditions such as this can be caused by any number of factors such as lack of maintenance, undersized or insufficiently sloped pipes, inlets with insufficient openings, or a general lack of inlets. The Town's inspection and street sweeping program indicates that maintenance is not a likely cause. Major construction would be needed to remedy an undersized system. Although field reconnaissance indicated a generally sound system, portions of the drainage system in the older parts of Town may soon reach the end of their service life and could need rehabilitation in coming years.

The Town also lacks a comprehensive inventory of its drainage structures. URS identified and located just under 700 inlets using Global Positioning System (GPS) equipment during the preparation of this report. In order to complete the inventory, connectivity between these inlets is still needed as well as pipe size and materials. Ideally, information including the approximate age of inlets and pipes would be required in order to develop a more accurate asset management database. Such a management system would enable better tracking of maintenance tasks and allow for a more accurate projection of future restoration costs.

There are currently 43 stormwater management basins and other stormwater best management practices (BMPs) within Centreville. Most of these are privately owned and maintained. The advantages and disadvantages of the Town assuming a more active role in the maintenance of these facilities is discussed in Section Five.

There are two Federal programs each deriving from the Clean Water Act that the Town needs to consider. The first, Total Maximum Daily Loads (TMDLs) has already resulted in expenditures by the Town as noted in Section Two. The second is the National Pollutant Discharge Elimination System (NPDES) permitting program for Municipal Separate Storm Sewer Systems (MS4s).

In 1996, the Corsica River was identified by the State of Maryland's list of water quality limited stream segments impaired by nutrients. TMDLs for nitrogen and phosphorus were subsequently determined. The goal of these TMDLs is to reduce high chlorophyll-a concentrations and maintain dissolved oxygen standards at levels where the designated uses for the Corsica River will be met. Load allocations were established for both point and nonpoint sources. While low flow allocations are based on design flows at the Centreville wastewater treatment plant, which is covered by a discharge permit, average and high flow allocations need to be achieved through nonpoint source pollution reduction programs. Efforts to meet the nonpoint source aspects need to be implemented or continued. Specifically, the Town's actions are integral to the success of the Corsica River Watershed Restoration Action Strategy. TMDLs have also been established for the Corsica River for Fecal Coliform, and TMDLs are pending at EPA for Polychlorinated Biphenyls (PCBs). It is also noted that the County and Town's Water Resources Element of the Comprehensive Plan has recently been adopted by both the County Commissioners and Town Council.

Hundreds of cities and counties across the country have their stormwater discharges regulated under the NPDES MS4 program. This program essentially presumes that non-point source pollution will be reduced in jurisdictions with a comprehensive and successful program. Inclusion in the permitting program is based on population and density. Requirements and policies of this program are set by the U.S. Environmental Protection Agency (EPA) but it is administered in Maryland by the State Department of the Environment (MDE). As previously noted, EPA has indicated its intent to expand the program to more geographic areas as well as focus on jurisdictions within critical watersheds such as the Chesapeake Bay. Eventually, Centreville may be required to obtain and subsequently comply with the conditions of an NPDES stormwater permit. EPA is also using the NPDES program as a vehicle to implement TMDLs in other parts of the country and many of the projects recently undertaken by Centreville on a voluntary basis may some day become mandatory.

The NPDES Phase II program has six components:

- Public education and outreach
- Public participation and involvement
- Illicit discharge detection and elimination
- Construction site stormwater runoff control
- Post construction stormwater management in new development and redevelopments
- Pollution prevention and good housekeeping for municipal operations and maintenance

Costs on a per capita basis vary significantly across the country, but a moderate program could be funded for \$10 per person annually or about \$35,000 annually.

### **Other Agencies Performing Services in Centreville**

While Town employees perform a majority of stormwater-related work in Centreville, there are other agencies that are also active. As previously noted, the Maryland State Highway Administration has responsibility for drainage system within State rights-of-way and Queen Anne's County performs reviews and inspections of stormwater management facilities related to new construction. MDE provides regulatory oversight for many of the water quality requirements such as stormwater management, erosion and sediment control, and TMDLs. Finally, the Maryland Department of Natural Resources (DNR) provided the funding for this Feasibility Study and also provided technical assistance with the preparation of the Corsica River Watershed Restoration Action Strategy (WRAS).

The Town of Centreville sponsored the WRAS that, according to DNR, makes the action strategies unique in Maryland. The actions recommended in the WRAS include urban stormwater retrofits, public education and outreach, and the implementation of low impact development strategies. Several recent Town projects including the wooded wetlands project adjacent to the wastewater treatment plant, the coastal plain outfall at the end of Banjo Lane, and the Low Impact Development (LID) Restoration Master Plan were all constructed or prepared as a result of the WRAS. Also, the nonprofit Corsica River Conservancy has multiple efforts aligned with the strategies. The Conservancy's four groups: Water Testing, Restoration, Education and Public Information, and Outreach are active throughout the watershed.

## **SECTION THREE. EXISTING PROGRAM AND PROJECTED FUTURE EXPENDITURES**

Expenditures coinciding with the Existing Program activities, as detailed in Section Two, have been summarized into spreadsheet format provided in Appendix A. It is assumed that the development and implementation of a stormwater utility would likely take at least a year and therefore the expenditures are shown in Year 0. These expenditures were projected out five years using an escalation factor of 2.5 percent to present more than just a “snapshot” of needs and approaches.

Projected future costs coinciding with program improvements were derived by interviews with Town personnel, field work performed by URS, and review of provided documents. Three potential levels of service (LOS) were evaluated and are also shown on the spreadsheet entitled Estimates of Expenditures in Appendix A.

### **Level of Service One – “Essential”**

Level of Service One includes the Existing Program as summarized in Section Two as well as hardware and software costs that would be incurred should a stormwater utility be implemented. These would include establishing a new accounting and billing process and an estimate of \$20,000 spread over two years has been assumed. A figure of \$33,000 was used for the replacement of the Vac-tron (to account for price increases in five years from the current estimate of \$30,000) and \$100,000 assumed for the street sweeper (spread out over three years to lessen the impact). Level of Service One also includes payments into a capital recovery fund or bond payments to enable major capital projects to be undertaken such as drainage inlet and pipe repair and replacement as well as funds for maintenance of retrofit projects previously undertaken by the Town. Finally, a more detailed inventory of the drainage infrastructure (inlets, pipes, and outfalls) is also included.

### **Level of Service Two – “Enhanced”**

Level of Service Two includes Level of Service One expenditures plus projects that begin moving the Town towards a more proactive approach to managing stormwater. Principally among these is construction and subsequent maintenance of low impact stormwater management facilities as recommended in the LID Restoration Master Plan prepared by EcoSite, Inc. Level of Service Two also includes compliance with TMDLs and a placeholder of \$10,000 has been assigned until a program is better defined. These activities would necessitate additional staff time and, in addition, a 10 percent increase over current expenditures has been assumed.

### **Level of Service Three – “Optimal”**

Level of Service Three includes Level of Service Two expenditures but more aggressively advances the proactive approach. It includes a higher level of treatment per the LID Master Plan. More significantly, it includes the maintenance of stormwater management basins as well as payments into a capital recovery fund or bond payments to enable retrofits should the Town decide to assume this responsibility. (Please refer to the policy discussion located in Section Five). Finally, Level of Service Three also includes compliance with the NPDES MS4 permit program. Though Centreville is not currently required to obtain a permit for its stormwater discharges, pending changes in the program by EPA could one day necessitate such coverage. A per capita cost of \$10 is being used which is a rough nationwide estimate of program costs. These activities would also necessitate additional staff time and a 20 percent increase over current expenditures has been assumed.

## **SECTION FOUR. REVENUE COLLECTION FRAMEWORK**

There is a direct correlation between amount of impervious surface and the rate and volume of runoff resulting from storm events on any given property. Since this runoff is handled by a public storm conveyance system once it leaves the property, in a stormwater utility scenario, those contributing more flow should be responsible for contributing more revenue as well. Rates for water, sewer, and electric services are determined in a similar fashion. In the case of stormwater though, there is no way to place a meter to measure runoff so the use of Equivalent Residential Units (ERUs) was developed as a commonly accepted and equitable measure. ERUs are intended to represent the amount of imperviousness on an average residential parcel and provide a common measure to compare residential and nonresidential properties. For example, if an ERU of 2,500 square feet is assigned, a property with 10,000 square feet of impervious coverage would represent four ERUs. Other mechanisms do exist that are similar but this study principally followed the ERU concept.

If a stormwater utility is to be formed, the fee level associated with the program requirements would need to be established and the residents' and merchants' willingness to pay determined. It also needs to be determined how the State's and Town's roads will be handled and what sort of credits could be put into place to recognize those areas already providing stormwater management. Finally, other funds need to be accounted for such as grants which may be available to supplement the program.

### **Stormwater Utility Fees**

The impervious coverage associated with five land uses in Centreville (single family residential, multi-family residential, commercial / industrial, public / institutional, and roads) was estimated through GIS evaluations. (See Figure 3.) These evaluations indicated that the amount of impervious surface for the average single-family detached residential property in Centreville is approximately 3,200 square feet. Therefore, this figure is used as the ERU. The number of ERUs for each of the land uses was determined by simply dividing the total calculated impervious coverage by the ERU figure of 3,200 square feet.

A framework for deriving revenues under this concept is shown in Appendix B. This spreadsheet includes the square footage of impervious coverage and the ensuing number of ERUs associated with the five principle land uses: single family residential, multi family residential, commercial / industrial, public / institutional, and roads.

Again referring to the Revenue Collection Framework spreadsheet, the column Existing Program (no SW utility) shows that revenues for current expenditures are derived solely from general fund transfers. Since the Existing Program as defined in Section Three represents staff time only, grants under this column are shown as zero even though Centreville has a demonstrated history of success in obtaining grants (such as the DNR grant used to fund this study).

The column Example Unit Rate shows how much revenue would be collected from each land use category with an ERU rate of \$1.00. These unit values were extrapolated for other ERU rates (not shown) such that rates corresponding to each level of service could be estimated. These are shown in columns Existing Program, Level of Service One, Level of Service Two, and Level of Service Three. Note that the latter Existing Program column differs from the former Existing Program (no SW utility) column in that it projects expenditures five years into the future, assumes that general fund transfers cease, and shows continued success obtaining grants to offset program costs.

Alternatives to this type of ERU approach exist. The impervious amount of cover on each and every residential parcel could be determined. This approach would likely result in a more accurate and equitable overall assessment but could be an administrative burden as there are over 1,300 single family residential properties in Centreville. Conversely, a rate could be determined for each residential zoning district by accounting for relative differences in lot sizes and building footprints among the zones.

In order to provide an evaluation of options, the 2007 Stormwater Utility Survey prepared by Black and Veatch, which received responses from 70 utilities around the country, was reviewed in this context. It found that 39 percent of respondents determined rates on an individual parcel basis and another 16 percent use a multi-tiered or by-zoning district approach. The Survey also found that 45 percent use a single tier basis as was utilized in the study. Other variations include what some utilities refer to as a development intensity factor which is essentially a ratio of impervious cover to total lot area.

A single or tiered rate is far simpler and less costly to administer. This is important as Centreville is a small municipality and does not have the same administrative capacity as the larger cities that have implemented stormwater utilities. However, this approach does not provide an incentive to reduce impervious cover on single family parcels (unless structured as part of a credit program as described in following sections) which could be an important goal of the Town. If lot-specific rates were used instead of a single or district-wide rate, a mechanism would be needed to periodically update the impervious coverage for each lot. Commonly used methods include the tracking of building permits or new aerial photographs and subsequent re-assessment every few years.

### **Credits and Exemptions**

Stormwater management practices employed on some properties may result in a lesser runoff contribution to the drainage system than comparable properties. Examples include detention / retention basins maintained by homeowners associations or disconnecting impervious areas (discharging roof downspouts onto green areas instead of paved areas), installing rain barrels, or placing porous pavement in lieu of concrete or asphalt by commercial or industrial property owners. Since these types of activities theoretically reduce the burden on the agency responsible for drainage, various credit programs have been developed. Less quantifiable, but still worthy of credits, are programs such as public education activities. Similarly, lot characteristics such as soil types or vegetation could be considered for credits as well but these are much more difficult to define.

For this study, a credit for the approximate 660 residential properties draining to privately-maintained detention or retention basins was assumed. Also, placeholders for two commercial / industrial credits were included. For demonstration purposes, these were shown as 25 percent. In other words, if the ERU rate was set at \$1.00, these residences and businesses would be assessed a rate of \$0.75.

A thorough assessment of credit programs nationwide was prepared by AMEC Earth and Environmental in 2007. They compiled data from 50 utilities in all areas of the country. When asked why certain types of credits were not employed, it was commonly answered that the combined cost to the utility to administer the credit as well as the applicant to apply for it often greatly exceeded the amount of the credit. Such a program would complicate a fee system that otherwise should be as simple as possible and would also necessitate audits to assure that the rationale for a credit, such as an on-site detention/retention basin, is functioning properly. Another approach would be to allow credits in non-residential situations only, but then use utility revenues to fund programs in residential areas such as rain barrel installations. Still, a system without credits provides little in the way of incentives for residents to reduce their contribution to the system and therefore should be considered if the Town Council opts to begin utility implementation. Finally, any credit program needs to be based on clear goals and objectives and not done in a piecemeal fashion.

Tax exempt properties, such as State and County lands, churches, or not-for-profit enterprises, create another, often difficult situation. On one hand, they are exempt from property taxes and a stormwater utility fee is essentially a property-based fee. On the other hand, the impervious surfaces on these properties and the resulting runoff must be managed as with any other property. Though the legalities of such fee assessments vary from state to state, courts have typically ruled that assessing a stormwater utility fee on tax-exempt properties is legitimate. This assessment assumed that tax-exempt properties in Centreville would contribute to a stormwater utility in the same way that every other property would. (State and County buildings, while exempt from Town property tax, pay water and sewer fees based on usage.)

The exception to this would be public roadways as these are most often owned by the jurisdiction proposing the utility. For this study it was assumed that roadways, both State and Town, would be exempted. As shown in the Revenue Collection Framework spreadsheet, these make up about a third of the impervious cover in Centreville. If this exemption were not included, the overall rates would decrease accordingly but would also result in the Town essentially paying a fee to itself. However, the decision could be made to exempt Town roads but not those roads owned by the State. Such a decision could have other ramifications. For comparison, the Black and Veatch survey found that 61 percent of utilities exempt roadways.

### **Assessment**

The Revenue Collection Framework spreadsheet provided in Appendix B is intended to demonstrate how revenues would be collected. It is based on numerous assumptions and the rates shown are for example only and should not be used for any type of budgeting projection. In addition to fine-tuning the impervious cover calculations, decisions regarding transfer amounts from the general fund, inclusion or exclusion of grants, and appropriateness and magnitude of credits and exemptions would need to be made before deriving any accurate assessment. These would be the focus of the second phase.

The Black and Veatch Survey also inquired as to the adequacy of program funding. It found that only 8 percent are able to meet all needs, 39 percent meet most needs, and 40 percent meet most urgent needs. Conversely, 13 percent stated available funds are not adequate to meet urgent needs. This indicates that utilities by and large are somewhat underfunded, but this is not a situation unique to stormwater utilities.



### Figure 3

## **SECTION FIVE. RECOMMENDATIONS**

### **Overview**

This Study sought to provide a framework for a stormwater utility and establish its feasibility. The creation of a stormwater utility in Centreville, with its own revenue based on impervious cover, would result in a stable, equitable, and dedicated funding source. It is recommended that the Town proceed with the second phase to resolve the issues highlighted below.

Assuming a second phase is initiated, the Town should anticipate that there will be multiple perspectives to be balanced and concerns to be considered. However, the Town and its residents should keep in mind that the “no action” alternative is not desirable. At the very least, it is recommended that internal changes be implemented such that costs and expenditures related to stormwater are more apparent. If Centreville becomes permitted under mandates such as the NPDES program, accurate accounting could make it easier to demonstrate compliance.

Since Centreville derives a substantial portion of its revenues from property taxes, the Town should be aware that if a utility funding mechanism is not adopted, a somewhat inequitable system will continue to exist. Property taxes are based on assessed value but a large, mostly impervious parcel may pay less in property taxes than a smaller parcel with less impervious surfaces.

It is recommended that the Town create a citizen advisory committee to assure that stakeholders such as business organizations, residential groups, churches, other governmental organizations, etc., are adequately represented in the utility development process. This will better assure that the program developed matches resident’s needs and expectations. Furthermore, having community leaders involved in the decision-making process could help with community buy-in. If utility development does proceed, at least one, if not more, public meetings would be advisable to better determine residents’ and merchants’ willingness-to-pay.

### **Utility Rates**

If a utility is implemented, the basis for the fee will need to be decided. This study was based on the assumption that all residential properties pay the same ERU rate regardless of their size. From an administrative approach, this is certainly the most expedient method, but could result in lots with lesser amounts of impervious coverage subsidizing lots with greater amounts. The Town has the option of determining the impervious coverage either on each and every lot or by zoning district. The parcel-by-parcel approach could provide an incentive for homeowners to reduce the impervious cover on their lot but needs to be weighed against the increased costs to determine the degree of imperviousness. The zoning district average approach, more or less, balances administrative efficiency with equity. A variation to these approaches would be to use a development intensity factor which is a ratio of impervious cover to total lot area.

Some jurisdictions have found it advantageous to enact a low fee initially and then increase it gradually over time. This has the benefit of segueing to a new revenue collection method and softening the impact of the new fee. However, proceeding in this manner could prove unwise if the initial rate is set too low. Once residents begin paying a fee, they will expect to see some results and if the program is underfunded, public support could waiver. It may be better to set the fee based on a five year projection of program expenditures.

Whatever rate is determined and allowances or credits offered, the overall collection program will need to be equitable in that those contributing greater loads to the drainage system pay a proportionally greater amount than those contributing lesser loads. There will also need to be a clear relationship between the stormwater expenditures and the collected revenues. If a utility fee is implemented, it cannot be used for non-stormwater purposes or placed in the general coffers for other uses.

### **Expenditures and Revenue Estimates**

Another recommendation relates to the spreadsheet assessment shown in Appendix A. The expenditure portion of this was based on a combination of field reconnaissance and interviews with Town personnel. These estimates would need to be refined. If a utility is implemented and then legally challenged, the Town will need to clearly show that the basis for the fee and the anticipated expenditures are reasonably accurate. If it is found that revenues significantly in excess of needs are being collected, the justification for the utility could be compromised.

The revenue collection portion of the spreadsheet is based on an approximation of impervious coverage (from 2008 aerial photography) using GIS shape files. It is likely that more recent aerial photography with a more exacting calculation of impervious surfaces would be needed prior to the enactment of a stormwater utility. It is noted that the limited scope of work for this Study did not allow for field verification of imperviousness calculations.

A mechanism will also be needed to update the impervious calculations. Assuming Centreville utilizes the ERU concept, either Town-wide or by zoning district, impervious calculations would not be needed in residential areas. However, a tracking mechanism would be needed if a parcel-by-parcel approach was used as well as for non-residential properties such that building additions or parking lot expansions are included in fee calculations. Aerial photographs are periodically taken, but years could go by between flights and revenue could be lost if not up-to-date. A better process may be to track additions and expansions through the building permit process and manually update the billing records of the affected properties. Finally, an appeals mechanism will also be needed for parcels that may be erroneously calculated.

### **Credits and Exemptions**

As noted in Section Four, the use of credits and exemptions needs to be carefully evaluated.

There are 43 stormwater management structures in Centreville of which 41 are privately owned and maintained. If these will remain in private hands, a credit may need to be established for their residents as discussed herein. Alternatively, the Town could seek to assume the maintenance responsibilities in which case a credit would not be appropriate (please see below). In fact, the increased costs accordingly would need to be accounted for. Some jurisdictions are taking over the maintenance of private basins under the premise that these entities often lack the financial and technical resources to do so and that public maintenance may eventually be required by the regulatory agencies. Credits could also be established for residents but the administrative burden of managing this aspect of the program may be prohibitive.

Another approach would be to allow credits in non-residential situations only, but then use utility revenues to fund grant programs in residential areas such as rain barrel installations. Similarly, a business could seek a reduction if it underwrites a public education effort or stream clean up. Since the number of businesses is much smaller than the number of residences, administrative costs would be comparatively less. Any credit program would need to be as simplistic as possible and enacted with clear goals and objectives and not piecemeal.

## **Policy Implications**

One of the most difficult issues regarding surface water management in Maryland and throughout the country is the reliance on private entities for the maintenance of stormwater management structures.

The problem is twofold. First, while homeowner associations (HOAs), in general, perform minimum upkeep like grass cutting, other tasks such as the control of invasive plants, repair of eroded banks, or removal of obstructions from outlets often are not performed which can increase future major maintenance costs. This situation will be compounded as stormwater practices shift away from centralized basins to more dispersed BMPs since the number of structures or facilities needing maintenance will grow more quickly and expertise to address these environmentally complex structures more difficult to obtain. (It should be noted that the Maryland Stormwater Act of 2007 and the ensuing Regulations generally required multiple BMPs and only allow centralized facilities as a last resort.)

Second, even if minor maintenance activities are adequately performed, it is doubtful that many HOAs are setting money aside for major maintenance such as reconstruction which can cost upwards of \$50,000 and, in certain cases much more, depending on size and location of the facility.

Assumption of maintenance responsibilities by the Town would be advantageous for a number of reasons. HOA officers, who are often lay people, would be relieved from the burden of maintaining their community's basins and BMPs better assuring the public at-large that this critical aspect of the overall drainage system is functioning properly. Total expenditures would be reduced if a single agency performed the maintenance work and / or oversaw contractors due to economies of scale. Most importantly, water quality in the Town would be improved through enhanced maintenance.

There are, of course, potential downsides that need to be considered as well. The costs associated with annual maintenance as well as the inevitable retrofits could significantly increase revenues needed to run the stormwater program. The Town could seek upfront payments from HOAs in exchange for relieving them of their responsibilities; however, agreeing to a reasonable amount could be problematic. If underestimated, increased revenues would be needed from other portions of the Town potentially raising fairness issues. However, HOA residents could counter-argue that their subdivisions have stormwater controls whereas many parts of Centreville do not and they could therefore claim that residents in other parts of Town are the ones being subsidized.

In the end, any such policy change would need to be fully vetted in the public arena with advantages and disadvantages fully explored.

## **Legal Issues**

The legal consequences of enacting a stormwater utility in Centreville need to be evaluated in concert with the Town's Attorney. The Black and Veatch survey indicated that nearly one quarter of utilities are legally challenged. As noted, it is extremely important that a fee be established that is proportional to users' contributions to the system and is directly related to the amount of stormwater expenditures needed and reasonably anticipated. It is vitally important that the Town have the legal authority to enact such a fee.

## **Conclusion**

The final phase of utility implementation would necessitate two broad actions by the Town to effectively resolve the issues described in these recommendations:

**Create a Citizens Advisory Committee** – The Committee, comprised of a diverse group of stakeholders, would better define the program and assure that it matches residents’ and merchants’ expectations and willingness-to-pay. The Committee could also hold public forums on utility development. A clear mission with overall time frame would be needed from the Town to assure the group stays focused.

**Prepare a Business Plan** – A utility cannot be created without a solid foundation. A Business Plan which would build upon, but better detail and fine tune, the expenditure and revenue estimates presented herein is essential. The Plan would also address various implementation details and resolve policy issues.

This completes the Stormwater Utility Feasibility Study for the Town of Centreville. Some jurisdictions have conducted similar assessments only to decide that a utility is not appropriate for them at the current time or under existing conditions. In other words, there is nothing improper with evaluating the potential for utility development and then deciding to not pursue it further. However, proceeding without necessary due diligence and understanding of residents’ expectations and then failing in the implementation could be very problematic. This study is intended to provide the guidance necessary if a consensus is reached that a stormwater utility is best for Centreville.

# **APPENDIX A**

**CENTREVILLE, MARYLAND STORMWATER UTILITY FEASIBILITY STUDY**

**ESTIMATES OF EXPENDITURES**

| Escalation Factor   | 2.50 %           |                  |                  |                  |                  |                  |
|---|------------------|------------------|------------------|------------------|------------------|------------------|
|   | Year 0           | Year 1           | Year 2           | Year 3           | Year 4           | Year 5           |
| <b>Existing Program</b>   |                  |                  |                  |                  |                  |                  |
| Vac-tron (2 person crew @ 1/2 time)   | \$50,000         | \$51,300         | \$52,600         | \$53,900         | \$55,200         | \$56,600         |
| Sweeper truck (one employee @ full time)  | \$50,000         | \$51,300         | \$52,600         | \$53,900         | \$55,200         | \$56,600         |
| Mowing and miscellaneous maintenance (equiv. to one person full time)             | \$50,000         | \$51,300         | \$52,600         | \$53,900         | \$55,200         | \$56,600         |
| Public Works Superintendent (1/4 time)  | \$20,000         | \$20,500         | \$21,000         | \$21,500         | \$22,000         | \$22,600         |
| Watershed Manager (1/4 time)  | \$25,000         | \$25,600         | \$26,200         | \$26,900         | \$27,600         | \$28,300         |
| <b>Existing Program</b>   | <b>\$195,000</b> | <b>\$200,000</b> | <b>\$205,000</b> | <b>\$210,100</b> | <b>\$215,200</b> | <b>\$220,700</b> |
| <b>Level of Service One - Essential</b>   |                  |                  |                  |                  |                  |                  |
| Utility Set Up Costs  | \$10,000         | \$10,000         | \$10,000         | \$0              | \$0              | \$0              |
| Capital Recovery Fund or Bond Payments for Capital Projects                       | \$25,000         | \$25,000         | \$25,625         | \$26,266         | \$26,922         | \$27,595         |
| Replacement of Vac-tron   | \$0              | \$0              | \$0              | \$0              | \$0              | \$33,000         |
| Replacement of Street Sweeper   | \$0              | \$0              | \$33,000         | \$33,000         | \$33,000         | \$0              |
| Maintenance of Previously Completed Retrofit Projects                             | \$5,000          | \$5,000          | \$5,125          | \$5,253          | \$5,384          | \$5,519          |
| Preparation of Drainage Inventory   | \$10,000         | \$10,000         | \$0              | \$0              | \$0              | \$0              |
| <b>Level of Service One Subtotal (incl. Existing Program)</b>                     | <b>\$250,000</b> | <b>\$278,750</b> | <b>\$274,619</b> | <b>\$280,507</b> | <b>\$286,814</b> |                  |
| <b>Level of Service Two - Enhanced</b>  |                  |                  |                  |                  |                  |                  |
| Additional staff time (10 percent increase over existing program)                 | \$20,000         | \$20,000         | \$20,500         | \$21,010         | \$21,520         | \$22,070         |
| LID Restoration Projects (control of 1 inch storm event)                          | \$89,000         | \$91,225         | \$93,506         | \$95,843         | \$98,239         | \$100,689        |
| LID Projects Maintenance  | \$12,500         | \$12,813         | \$13,133         | \$13,461         | \$13,798         | \$14,136         |
| Nonpoint Source Reduction Programs (TMDLs) *                                      | \$10,000         | \$10,250         | \$10,506         | \$10,769         | \$11,038         | \$11,313         |
| <b>Level of Service Two Subtotal (incl. Exist. Prog. and LOS One)</b>             | <b>\$381,500</b> | <b>\$413,538</b> | <b>\$412,773</b> | <b>\$422,100</b> | <b>\$431,960</b> |                  |
| <b>Level of Service Three - Optimal</b>   |                  |                  |                  |                  |                  |                  |
| Additional staff time (20 percent increase over existing program)                 | \$40,000         | \$41,000         | \$42,020         | \$43,040         | \$44,140         | \$45,280         |
| LID Restoration Projects (higher level of control)                                | \$77,000         | \$78,925         | \$80,898         | \$82,921         | \$84,994         | \$87,119         |
| Stormwater Management Basin Maintenance (\$2,000 each x 50 facilities)            | \$100,000        | \$102,500        | \$105,063        | \$107,689        | \$110,381        | \$113,149        |
| Capital Recovery Fund or Bond Payments for Basin Retrofits                        | \$50,000         | \$51,250         | \$52,531         | \$53,845         | \$55,191         | \$56,579         |
| Permitting Compliance (NPDES) *   | \$35,000         | \$35,875         | \$36,772         | \$37,691         | \$38,633         | \$39,599         |
| <b>Level of Service Three Subtotal (incl. Exist. Program and LOS One and Two)</b> | <b>\$683,500</b> | <b>\$723,088</b> | <b>\$730,057</b> | <b>\$747,285</b> | <b>\$765,299</b> |                  |

\* = regulatory programs

# **APPENDIX B**



**CENTREVILLE, MARYLAND STORMWATER UTILITY FEASIBILITY STUDY**

**REVENUE COLLECTION FRAMEWORK**

| ERU size                                     | 3,200 square feet | ft <sup>2</sup> | ERU's | Existing Program<br>(no SW utility) | Example Unit Rate | Existing Program | Level of    | Level of    | Level of      |
|--|-------------------|-----------------|-------|-------------------------------------|-------------------|------------------|-------------|-------------|---------------|
|  |                   |                 |       |                                     |                   |                  | Service One | Service Two | Service Three |
| Unit Rate per ERU/Month                      |                   |                 |       | \$0.00                              | \$1.00            | \$5.87           | \$8.15      | \$13.14     | \$24.61       |
| Unit Rate per 1,000 sq. ft./month            |                   |                 |       | \$0.00                              | \$0.31            | \$1.83           | \$2.55      | \$4.11      | \$7.69        |
| <b>Utility Revenue</b>                       |                   |                 |       | \$0                                 | \$16,002          | \$93,959         | \$130,350   | \$210,243   | \$393,724     |
| Single Family Residential                    | 4,267,138         | 1,333           |       | \$0                                 | \$608             | \$3,568          | \$4,950     | \$7,984     | \$14,952      |
| Multi Family Residential                     | 162,043           | 51              |       | \$0                                 | \$10,092          | \$59,257         | \$82,207    | \$132,593   | \$248,308     |
| Commercial / Industrial                      | 2,691,137         | 841             |       | \$0                                 | \$5,250           | \$30,827         | \$42,767    | \$68,979    | \$129,178     |
| Public / Institutional                       | 1,400,018         | 438             |       | \$0                                 | \$14,840          | \$87,139         | \$120,889   | \$194,983   | \$365,147     |
| Roads  | 3,957,426         | 1,237           |       | \$0                                 | \$46,792          | \$274,750        | \$381,164   | \$614,782   | \$1,151,308   |
| <b>Utility Revenue Subtotal</b>              |                   |                 |       | \$0                                 |                   |                  |             |             |               |
| <b>Other Revenue</b>                         |                   |                 |       | \$195,000                           | \$0               | \$0              | \$0         | \$0         | \$0           |
| Transfer from General Fund                   |                   |                 |       | \$0                                 | \$50,000          | \$50,000         | \$50,000    | \$50,000    | \$50,000      |
| Grants                                       |                   |                 |       | \$195,000                           | \$96,792          | \$324,750        | \$431,164   | \$664,782   | \$1,201,308   |
| <b>Utility and Other Revenue Subtotal</b>    |                   |                 |       |                                     |                   |                  |             |             |               |
| <b>Credits</b>                               |                   |                 |       | \$0.00                              | \$0.25            | \$1.47           | \$2.04      | \$3.28      | \$6.15        |
| Credit Amount                                | 25.00%            |                 | ERU's | \$0                                 | (\$1,980)         | (\$11,626)       | (\$16,129)  | (\$26,015)  | (\$48,718)    |
| Residences with SWM basins                   |                   |                 | 660   | \$0                                 | (\$600)           | (\$3,523)        | (\$4,888)   | (\$7,883)   | (\$14,763)    |
| Commercial Credit 1 (for example)            |                   |                 | 200   | \$0                                 | (\$300)           | (\$1,762)        | (\$2,444)   | (\$3,942)   | (\$7,382)     |
| Commercial Credit 2 (for example)            |                   |                 | 100   | \$0                                 | (\$2,880)         | (\$16,911)       | (\$23,460)  | (\$37,840)  | (\$70,862)    |
| <b>Credits Subtotal</b>                      |                   |                 |       | \$0                                 |                   |                  |             |             |               |
| <b>Exemptions</b>                            |                   |                 |       | \$0.00                              | \$1.00            | \$5.87           | \$8.15      | \$13.14     | \$24.61       |
| Exemption Amount                             |                   |                 | ERU's | \$0                                 | (\$14,840)        | (\$87,139)       | (\$120,889) | (\$194,983) | (\$365,147)   |
| Roads  | 3,957,426         | 1,237           |       | \$0                                 | (\$14,840)        | (\$87,139)       | (\$120,889) | (\$194,983) | (\$365,147)   |
| <b>Exemptions Subtotal</b>                   |                   |                 |       | \$0                                 |                   |                  |             |             |               |
| <b>Credits and Exemptions Subtotal</b>       |                   |                 |       | \$0                                 | (\$17,720)        | (\$104,050)      | (\$144,350) | (\$232,823) | (\$436,009)   |
| <b>Revenues minus Credits and Exemptions</b> |                   |                 |       | \$195,000                           | \$79,071          | \$220,700        | \$286,814   | \$431,960   | \$765,299     |

the 1990s, the number of people with a mental health problem has increased in the UK (Mental Health Act 1983).

There is a growing awareness of the need to improve the lives of people with mental health problems. The Department of Health (1999) has set out a vision of a new mental health system, which will be based on the following principles:

- (i) People with mental health problems should be treated as individuals, with their own needs and wishes.
- (ii) People with mental health problems should be given the opportunity to participate in decisions about their care and treatment.
- (iii) People with mental health problems should be given the opportunity to live in their own homes and communities.

There is a growing awareness of the need to improve the lives of people with mental health problems.

The Department of Health (1999) has set out a vision of a new mental health system, which will be based on the following principles:

- (i) People with mental health problems should be treated as individuals, with their own needs and wishes.
- (ii) People with mental health problems should be given the opportunity to participate in decisions about their care and treatment.
- (iii) People with mental health problems should be given the opportunity to live in their own homes and communities.

There is a growing awareness of the need to improve the lives of people with mental health problems.

The Department of Health (1999) has set out a vision of a new mental health system, which will be based on the following principles:

- (i) People with mental health problems should be treated as individuals, with their own needs and wishes.
- (ii) People with mental health problems should be given the opportunity to participate in decisions about their care and treatment.
- (iii) People with mental health problems should be given the opportunity to live in their own homes and communities.

There is a growing awareness of the need to improve the lives of people with mental health problems.

The Department of Health (1999) has set out a vision of a new mental health system, which will be based on the following principles:

- (i) People with mental health problems should be treated as individuals, with their own needs and wishes.
- (ii) People with mental health problems should be given the opportunity to participate in decisions about their care and treatment.
- (iii) People with mental health problems should be given the opportunity to live in their own homes and communities.

# **ATTACHMENT 1**

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5038                  | Inlet          | A J (Double)          | street   | Brick    |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 3:00            | Overcast |

| Development | Address Prefix | Street  | address_suffix           |
|-------------|----------------|---------|--------------------------|
|             |                | Kidwell | 50' east of Tilghman Ave |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | con/asp    | 0               |                          |

| Grate Type   | Grate Condition | Grate Defect Description |
|--------------|-----------------|--------------------------|
| Parallel Bar | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                                | Step Material | Step Nummer | Step Condition | Step Defect Description |
|-------------------------------------|---------------|-------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> |               | 2           | 0              | cast iron material      |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

**Condition Key: 0 = Good 3 = Fair 5 = Poor**

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5039                         | Inlet                 | Double A J                   | street          | Brick           |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 2:00                   | Overcast       |

|                    |                       |                |                       |
|--------------------|-----------------------|----------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>  | <b>address_suffix</b> |
|                    | 208                   | Kidwell Avenue | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Parallel Bar      | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Concrete                   | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5060                  | Inlet          | B                     | street   | Brick    |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 1:00            | Overcast |

| Development | Address Prefix | Street               | address_suffix |
|-------------|----------------|----------------------|----------------|
|             | 319            | Little Kidwell Drive | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type   | Grate Condition | Grate Defect Description |
|--------------|-----------------|--------------------------|
| Parallel Bar | 0               |                          |

| Inlet                    | Inlet Condition | Inlet Defect Description |
|--------------------------|-----------------|--------------------------|
| <input type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5061                  | Inlet          | Double "B"            | street   | Brick    |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 1:00            | Overcast |

| Development | Address Prefix | Street               | address_suffix |
|-------------|----------------|----------------------|----------------|
|             | 324            | Little Kidwell Drive |                |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type   | Grate Condition | Grate Defect Description |
|--------------|-----------------|--------------------------|
| Parallel Bar | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5071                         | Inlet                 | 2 X B                        | street          | Brick           |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 2:00                   | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    |                       | Brown Street  | at white building     |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Parallel Bar      | 0                      |                                 |

|                          |                        |                                 |
|--------------------------|------------------------|---------------------------------|
| <b>Inlet</b>             | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                                     |                      |                    |                       |                                |
|-------------------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>                         | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input checked="" type="checkbox"/> | PVC                  | 3                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                | 0                     |                                |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5076                  | Inlet          | B                     | street   | Brick    |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 2:00            | Overcast |

| Development | Address Prefix | Street   | address_suffix |
|-------------|----------------|----------|----------------|
|             | 110            | Brown St | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Asp/con    | 0               |                          |

| Grate Type   | Grate Condition | Grate Defect Description |
|--------------|-----------------|--------------------------|
| Parallel Bar | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5108                         | Inlet                 | A J                          | Street          | Brick           |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 11:00                  | Overcast       |

|                    |                       |                    |                       |
|--------------------|-----------------------|--------------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>      | <b>address_suffix</b> |
|                    | 120                   | Hope Road (Rt 305) | Front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | Asphalt           | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Reticuline        | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 3                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5112                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 1:00            | Sunny   |

| Development | Address Prefix | Street    | address_suffix |
|-------------|----------------|-----------|----------------|
|             | 204            | Hope Road | (305) front of |

| Frame                               | Frame_mat | Frame_surf  | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|-------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | con/asphalt | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                    | Inlet Condition | Inlet Defect Description |
|--------------------------|-----------------|--------------------------|
| <input type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5113                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 1:00            | Sunny   |

| Development | Address Prefix | Street  | address_suffix |
|-------------|----------------|---------|----------------|
|             | 213            | Hope Rd | (305) front of |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | asphalt    | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                    | Inlet Condition | Inlet Defect Description |
|--------------------------|-----------------|--------------------------|
| <input type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5120                         | Inlet                 | AJ                           | street          | Brick           |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 2:00                   | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 116                   | Kings Ct      | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | con/asphalt       | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Reticuline        | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5122                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street   | address_suffix |
|-------------|----------------|----------|----------------|
|             | 115            | Kings Ct | front of       |

| Frame                               | Frame_mat | Frame_surf  | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|-------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | con/asphalt | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5123                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street   | address_suffix |
|-------------|----------------|----------|----------------|
|             | 138            | Kings Ct | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | con/aspalt | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5124                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 12:00           | Sunny   |

| Development | Address Prefix | Street       | address_suffix |
|-------------|----------------|--------------|----------------|
|             | 235            | Heritage Way | side of        |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                                | Step Material | Step Nummer | Step Condition | Step Defect Description |
|-------------------------------------|---------------|-------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | PVC           | 2           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5127                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 12:00           | Sunny   |

| Development | Address Prefix | Street       | address_suffix |
|-------------|----------------|--------------|----------------|
|             | 235            | Heritage Way | Side of        |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                                | Step Material | Step Numner | Step Condition | Step Defect Description |
|-------------------------------------|---------------|-------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | PVC           | 1           | 0              |                         |

| Wall                     | Wall Material | Wall Condition | Wall Defect Description |
|--------------------------|---------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5128                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 12:00                  | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 236                   | Heritage Way  | side od , at pond     |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Numner</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5131                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 12:00           | Sunny   |

| Development | Address Prefix | Street       | address_suffix                 |
|-------------|----------------|--------------|--------------------------------|
|             |                | Heritage Way | Top of retention Pond at fence |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5133                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 1:00                   | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 148                   | Autumn Lane   | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 2                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5135                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 1:00                   | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 135                   | Autumn Lane   | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5139                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street      | address_suffix |
|-------------|----------------|-------------|----------------|
|             | 219            | Autumn Lane | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5140                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street      | address_suffix |
|-------------|----------------|-------------|----------------|
|             | 225            | Autumn Lane | Front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5141                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 12:00           | Sunny   |

| Development | Address Prefix | Street                   | address_suffix |
|-------------|----------------|--------------------------|----------------|
|             | 305            | Inter Walnut St & Hop Rd |                |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | con/asp    | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5142                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 12:00           | Sunny   |

| Development | Address Prefix | Street                       | address_suffix |
|-------------|----------------|------------------------------|----------------|
|             | 305            | Inter of Walnut St & Hope Rd |                |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5143                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 11:00                  | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 138                   | Cypress Ct    | Front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 1                        |                                      |

|                                     |                      |                    |                       |                                |
|-------------------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>                         | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input checked="" type="checkbox"/> | PVC                  | 3                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5145                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 11:00           | Sunny   |

| Development | Address Prefix | Street      | address_suffix |
|-------------|----------------|-------------|----------------|
|             | 160            | Cypress Ct. | Front of pond  |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 1                 |                               |

| Step                                | Step Material | Step Nummer | Step Condition | Step Defect Description |
|-------------------------------------|---------------|-------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | PVC           | 2           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5146                  | Inlet          | AJ                    | Street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 11:00           | Sunny   |

| Development | Address Prefix | Street            | address_suffix |
|-------------|----------------|-------------------|----------------|
|             |                | Pine St & Hope Rd |                |

| Frame                               | Frame_mat | Frame_surf  | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|-------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Con/Asphalt | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5147                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 11:00           | Sunny   |

| Development | Address Prefix | Street                  | address_suffix |
|-------------|----------------|-------------------------|----------------|
|             |                | Pine Street & Hope Road |                |

| Frame                               | Frame_mat | Frame_surf  | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|-------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Asphalt/con | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Concrete      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5159                  | Inlet          | cog                   |          | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/14/2010       | 9:00            | Overcast |

| Development | Address Prefix | Street        | address_suffix |
|-------------|----------------|---------------|----------------|
|             | 164            | Edenderry Ave | Front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5177                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/14/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street      | address_suffix |
|-------------|----------------|-------------|----------------|
|             | 108            | Gronard Ave | Front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5192                  | Inlet          | COG                   | Street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/14/2010       | 9:00            | Overcast |

| Development | Address Prefix | Street        | address_suffix |
|-------------|----------------|---------------|----------------|
|             | 136            | Banbridge Ave |                |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Concrete   | 0               | Concrete                 |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5210                  | Junction Box   | manhole               | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/14/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street | address_suffix                             |
|-------------|----------------|--------|--|
|             |                |        | Inter of FieldCroft Way and Brook Run Lane |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Sphalt     | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                    | Inlet Condition | Inlet Defect Description |
|--------------------------|-----------------|--------------------------|
| <input type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5247                         | Inlet                 | COG                          | Street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 10:00                  | Overcast       |

|                    |                       |                |                       |
|--------------------|-----------------------|----------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>  | <b>address_suffix</b> |
|                    | 246                   | Northfield Way | Front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | Concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5285                  | Inlet          | COG                   | Street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/14/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street           | address_suffix |
|-------------|----------------|------------------|----------------|
|             | 607            | Brookfield Drive | Front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | Concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 1                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5309                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 10:00                  | Overcast       |

|                    |                       |                |                       |
|--------------------|-----------------------|----------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>  | <b>address_suffix</b> |
|                    | 109                   | East Meadow Dr | Front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | Concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5349                  | Inlet          | B                     | street   | Concrete |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street                      | address_suffix |
|-------------|----------------|-----------------------------|----------------|
|             |                | Inter of Windsor Ave & Newm |                |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type    | Grate Condition | Grate Defect Description   |
|---------------|-----------------|----------------------------|
| Perpendicular | 0               | Perpend bar (seized grate) |

| Inlet                    | Inlet Condition | Inlet Defect Description |
|--------------------------|-----------------|--------------------------|
| <input type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Concrete      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5352                  | Inlet          | AJ                    | street   | Brick    |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/14/2010       | 2:00            | Sunny   |

| Development | Address Prefix | Street       | address_suffix |
|-------------|----------------|--------------|----------------|
|             | 205            | Glandale Ave | across from    |

| Frame                               | Frame_mat | Frame_surf    | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|---------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | stone/asphalt | 3               |                          |

| Grate Type   | Grate Condition | Grate Defect Description |
|--------------|-----------------|--------------------------|
| Parallel Bar | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Brick         | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5353                         | Inlet                 | B                            | street          | Concrete        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/14/2010              | 3:00                   | Sunny          |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|--------------------|-----------------------|---------------|-----------------------|

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
|                   | 0                      |                                 |

|                          |                        |                                 |
|--------------------------|------------------------|---------------------------------|
| <b>Inlet</b>             | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Concrete             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5389                         | Inlet                 | AJ                           | street          |                 |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 1:00                   |                |

|                    |                       |                   |                             |
|--------------------|-----------------------|-------------------|-----------------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>     | <b>address_suffix</b>       |
|                    |                       | S. Liberty Street | Front of Millstream Park on |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | asphalt           | 3                      | frame sinking around asphalt    |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Reticuline        | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 5                      | curb displaced from structure   |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Numner</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                | 0                     |                                |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5395                  | Inlet          | cog/retic             | street   | Concrete |

| Inspection Date | Inspection Time | Weather |
|-----------------|-----------------|---------|
| 5/19/2010       | 1:00            | Sunny   |

| Development | Address Prefix | Street         | address_suffix       |
|-------------|----------------|----------------|----------------------|
|             | 415            | S. Commerce St | 100' south, front of |

| Frame                               | Frame_mat | Frame_surf       | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | asphalt/concrete | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Reticuline | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Concrete            | 0                    | 1                 |                               |

| Step                                | Step Material | Step Numner | Step Condition | Step Defect Description |
|-------------------------------------|---------------|-------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Aluminum      | 3           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Concrete      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5399                         | Inlet                 | cog                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 1:00                   | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    |                       | Ridgeview Ave |                       |

|                          |                  |                   |                        |                                 |
|--------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>             | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input type="checkbox"/> |                  |                   | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
|                   | 0                      |                                 |

|                          |                        |                                 |
|--------------------------|------------------------|---------------------------------|
| <b>Inlet</b>             | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input type="checkbox"/> | 0                      |                                 |

|                          |                            |                             |                          |                                      |
|--------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>        | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input type="checkbox"/> |                            | 0                           | 0                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Numner</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                          |                      |                       |                                |
|--------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>              | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input type="checkbox"/> |                      | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5411                         | Inlet                 | Reticuline                   | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 11:00                  | Overcast       |

|                    |                       |                 |                       |
|--------------------|-----------------------|-----------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b>   | <b>address_suffix</b> |
|                    |                       | Frederick Drive | at circle             |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | asphalt           | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Reticuline        | 0                      |                                 |

|                          |                        |                                 |
|--------------------------|------------------------|---------------------------------|
| <b>Inlet</b>             | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5412                  | Inlet          | COG                   | street   |          |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 11:00           | Overcast |

| Development | Address Prefix | Street         | address_suffix     |
|-------------|----------------|----------------|--------------------|
|             | 113            | Fredrick Drive | front of at circle |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 4                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5424                         | Inlet                 | cog                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 12:00                  | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 125                   | Comet Drive   | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 2                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Numner</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5425                         | Inlet                 | cog                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 11:00                  | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 125                   | Comet Drive   | across from           |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 2                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5432                  | Inlet          | cog                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 12:00           | Overcast |

| Development | Address Prefix | Street   | address_suffix |
|-------------|----------------|----------|----------------|
|             | 152            | Comet Dr | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5433                         | Inlet                 | cog                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 12:00                  | Overcast       |

|                    |                       |               |                               |
|--------------------|-----------------------|---------------|-------------------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b>         |
|                    |                       | Comet Drive   | end of circle across from 255 |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Concrete                   | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Numner</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                          |                      |                       |                                |
|--------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>              | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input type="checkbox"/> |                      | 0                     |                                |



# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5455                  | Inlet          | cog                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 11:00           | Overcast |

| Development | Address Prefix | Street           | address_suffix            |
|-------------|----------------|------------------|---------------------------|
|             |                | Taylor Mill Road | 100Yds W of Symphony Blvd |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
|            | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5495                         | Inlet                 |                              | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 10:00                  | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 631                   | Harmony Way   | front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 3                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5537                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street    | address_suffix |
|-------------|----------------|-----------|----------------|
|             | 122            | Encore Ct | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 1                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5574                  | Inlet          | COG                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street         | address_suffix |
|-------------|----------------|----------------|----------------|
|             | 227            | Orchestra Pace | Front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> |                     | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

|                              |                       |                              |                 |                 |
|------------------------------|-----------------------|------------------------------|-----------------|-----------------|
| <b>Structure Part Number</b> | <b>Structure Type</b> | <b>Structure Description</b> | <b>Location</b> | <b>Material</b> |
| 5594                         | Inlet                 | COG                          | street          | Pre Cast        |

|                        |                        |                |
|------------------------|------------------------|----------------|
| <b>Inspection Date</b> | <b>Inspection Time</b> | <b>Weather</b> |
| 5/19/2010              | 9:00                   | Overcast       |

|                    |                       |               |                       |
|--------------------|-----------------------|---------------|-----------------------|
| <b>Development</b> | <b>Address Prefix</b> | <b>Street</b> | <b>address_suffix</b> |
|                    | 223                   | Concerto Way  | Front of              |

|                                     |                  |                   |                        |                                 |
|-------------------------------------|------------------|-------------------|------------------------|---------------------------------|
| <b>Frame</b>                        | <b>Frame_mat</b> | <b>Frame_surf</b> | <b>Frame Condition</b> | <b>Frame Defect Description</b> |
| <input checked="" type="checkbox"/> | Cast Iron        | concrete          | 0                      |                                 |

|                   |                        |                                 |
|-------------------|------------------------|---------------------------------|
| <b>Grate Type</b> | <b>Grate Condition</b> | <b>Grate Defect Description</b> |
| Solid             | 0                      |                                 |

|                                     |                        |                                 |
|-------------------------------------|------------------------|---------------------------------|
| <b>Inlet</b>                        | <b>Inlet Condition</b> | <b>Inlet Defect Description</b> |
| <input checked="" type="checkbox"/> | 0                      |                                 |

|                                     |                            |                             |                          |                                      |
|-------------------------------------|----------------------------|-----------------------------|--------------------------|--------------------------------------|
| <b>Riser Ring</b>                   | <b>Riser Ring Material</b> | <b>Riser Ring Condition</b> | <b>Riser Ring Number</b> | <b>Riser Ring Defect Description</b> |
| <input checked="" type="checkbox"/> | Brick                      | 0                           | 1                        |                                      |

|                          |                      |                    |                       |                                |
|--------------------------|----------------------|--------------------|-----------------------|--------------------------------|
| <b>Step</b>              | <b>Step Material</b> | <b>Step Nummer</b> | <b>Step Condition</b> | <b>Step Defect Description</b> |
| <input type="checkbox"/> |                      | 0                  | 0                     |                                |

|                                     |                      |                       |                                |
|-------------------------------------|----------------------|-----------------------|--------------------------------|
| <b>Wall</b>                         | <b>Wall Material</b> | <b>Wall Condition</b> | <b>Wall Defect Description</b> |
| <input checked="" type="checkbox"/> | Pre Cast             | 0                     |                                |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

---

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5598                  | Inlet          | cog                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street     | address_suffix |
|-------------|----------------|------------|----------------|
|             | 133            | Sonata Way | front of       |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring               | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|--------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input type="checkbox"/> |                     | 0                    | 0                 |                               |

| Step                     | Step Material | Step Numner | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |

# INLET INSPECTION REPORT

Condition Key: 0 = Good 3 = Fair 5 = Poor

| Structure Part Number | Structure Type | Structure Description | Location | Material |
|-----------------------|----------------|-----------------------|----------|----------|
| 5626                  | Inlet          | cog                   | street   | Pre Cast |

| Inspection Date | Inspection Time | Weather  |
|-----------------|-----------------|----------|
| 5/19/2010       | 10:00           | Overcast |

| Development | Address Prefix | Street           | address_suffix             |
|-------------|----------------|------------------|----------------------------|
|             |                | Taylor Hill Road | 300 yds from Symphony Blvd |

| Frame                               | Frame_mat | Frame_surf | Frame Condition | Frame Defect Description |
|-------------------------------------|-----------|------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | Cast Iron | concrete   | 0               |                          |

| Grate Type | Grate Condition | Grate Defect Description |
|------------|-----------------|--------------------------|
| Solid      | 0               |                          |

| Inlet                               | Inlet Condition | Inlet Defect Description |
|-------------------------------------|-----------------|--------------------------|
| <input checked="" type="checkbox"/> | 0               |                          |

| Riser Ring                          | Riser Ring Material | Riser Ring Condition | Riser Ring Number | Riser Ring Defect Description |
|-------------------------------------|---------------------|----------------------|-------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Brick               | 0                    | 2                 |                               |

| Step                     | Step Material | Step Nummer | Step Condition | Step Defect Description |
|--------------------------|---------------|-------------|----------------|-------------------------|
| <input type="checkbox"/> |               | 0           | 0              |                         |

| Wall                                | Wall Material | Wall Condition | Wall Defect Description |
|-------------------------------------|---------------|----------------|-------------------------|
| <input checked="" type="checkbox"/> | Pre Cast      | 0              |                         |





# POND REPORT

**Facility No** 100      **County** Queen Anne's      **District**  
**Inspection Date** 06-May-10      **Inspection Time** 12:10:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**

**BMP Location** At the centerlink & Coursevall Dr, Front of MD 213

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment  |
|----------------|------------------|--------------------------|----------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |          |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |          |
| Phragmites     | Within Pond      | <input type="checkbox"/> |          |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 101      **County**      **District**  
**Inspection Date** 14-May-10      **Inspection Time** 1:03:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** MD Rte 213 at Food Lion

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Good      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 102      **County** Queen Anne's      **District**  
**Inspection Date** 06-May-10      **Inspection Time** 11:10:00 AM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Rear of Food Lion on Rt 213, Off Coursevall Drive, 300-400 yds

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Fair      | <input type="checkbox"/> |
| Outlet Channel | Fair      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 13      **County** Queen Anne's      **District**  
**Inspection Date** 11-May-10      **Inspection Time** 11:45:00 AM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Off Route 305 in Center Village, Side of 129 Kings Court

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component              | Condition | MWO                      |
|------------------------|-----------|--------------------------|
| Pond Bottom            | Fair      | <input type="checkbox"/> |
| Side Slope and Buffers | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Metal    | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Metal    | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment           |
|-------------------------------------|-------------------|
| <input checked="" type="checkbox"/> | Moderate to Heavy |

### Trash Issues

| Trash Present                       | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | minor   |
| <input type="checkbox"/>            | Minor   |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment  |
|----------------|------------------|--------------------------|----------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |          |
| Canada Thistle | Within Pond      | <input type="checkbox"/> |          |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |          |
| Trees          | Surrounding Pond | <input type="checkbox"/> |          |
| Trees          | Within Pond      | <input type="checkbox"/> |          |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

| Problem  | MWO                      |
|--|--------------------------|
| Large amount of Vegetation, Brush and Trees around pond. | <input type="checkbox"/> |

# POND REPORT

---

**Facility No** 14      **County** Queen Anne's      **District**  
**Inspection Date** 11-May-10      **Inspection Time** 12:35:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Off Route 305 in Centreville Village, ear of 138 and 134 Kings Court  
**Setting** Could not Find or Locate, appears to be a Marsh

---

**Erosion Issues**

**Sedimentation Issues**

**RipRap Issues**

**Riser and Trash Rack Issues**

**Principal Spillway Barrel Issues**

**Inadequate Vegetative Cover Issues**

**Debris Issues**

**Trash Issues**

**Unwanted\_Vegetation Issues**

**Bike Trails and Animal Burrows**

**Embankment Pond Issues**

**Other Issues**

# POND REPORT

**Facility No** 157      **County** Queen Anne's      **District**  
**Inspection Date** 11-May-10      **Inspection Time** 11:00:00 AM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Off Route 305 in Heritage Subdivsion, Side od 225 Autumn Court

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment  |
|----------------|------------------|--------------------------|----------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |          |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |          |
| Phragmites     | Within Pond      | <input type="checkbox"/> |          |

### Bike Trails and Animal Burrows

### Embankment Pond Issues

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Other Issues

| Problem                                   | MWO                      |
|---|--------------------------|
| Minor erosion on South West area of Pond. | <input type="checkbox"/> |

# POND REPORT

**Facility No** 158      **County** Queen Anne's      **District**  
**Inspection Date** 11-May-10      **Inspection Time** 10:15:00 AM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**

**BMP Location** Off Route 305 in Heritage Subdivision, Back of Heritage Court, Side of 236 Heritage C  
**Setting**

**Erosion Issues**

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

**Sedimentation Issues**

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

**RipRap Issues**

**Riser and Trash Rack Issues**

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

**Principal Spillway Barrel Issues**

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

**Inadequate Vegetative Cover Issues**

**Debris Issues**

**Trash Issues**

| Trash Present            | Comment    |
|--------------------------|------------|
| <input type="checkbox"/> | very minor |

**Unwanted\_Vegetation Issues**

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Within Pond      | <input type="checkbox"/> |         |

**Bike Trails and Animal Burrows**

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

**Embankment Pond Issues**

**Other Issues**

# POND REPORT

**Facility No** 187      **County** Queen Anne's      **District**  
**Inspection Date** 12-May-10      **Inspection Time** 12:11:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Side of Acme in Centreville Plaza, off Little Hut Lane

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Trash Issues

| Trash Present                       | Comment    |
|-------------------------------------|------------|
| <input checked="" type="checkbox"/> | Very Minor |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment                            |
|----------------|------------------|--------------------------|------------------------------------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |                                    |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails, Large amount within pond |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> | Large amount Surrounding pond      |
| Phragmites     | Within Pond      | <input type="checkbox"/> | Large smount within pond           |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

| Problem  | MWO                      |
|--|--------------------------|
| 6' Fence surrounding Pond, Could not access, Inspected outside of Fence. | <input type="checkbox"/> |



# POND REPORT

**Facility No** 2      **County** Queen Anne's      **District**  
**Inspection Date** 12-May-10      **Inspection Time** 1:47:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Rear of Ashley Mini Storage off Railroad Ave, Side of Center Park Apts., on Little Hut  
**Setting**

## Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

## Sedimentation Issues

| Component              | Condition | MWO                      |
|------------------------|-----------|--------------------------|
| Pond Bottom            | Fair      | <input type="checkbox"/> |
| Side Slope and Buffers | Good      | <input type="checkbox"/> |

## RipRap Issues

## Riser and Trash Rack Issues

## Principal Spillway Barrel Issues

## Inadequate Vegetative Cover Issues

## Debris Issues

| Debris Present                      | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

## Trash Issues

| Trash Present                       | Comment         |
|-------------------------------------|-----------------|
| <input checked="" type="checkbox"/> | garbage present |
| <input type="checkbox"/>            | Minor           |

## Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment                  |
|----------------|------------------|--------------------------|--------------------------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> | Minor to Moderate amount |
| Canada Thistle | Within Pond      | <input type="checkbox"/> | Moderate amount          |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> | Minor to Moderate amount |
| Phragmites     | Within Pond      | <input type="checkbox"/> | Moderate amount          |
| Trees          | Surrounding Pond | <input type="checkbox"/> | Minor to Moderate amount |
| Trees          | Within Pond      | <input type="checkbox"/> | Moderate amount          |

## Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

## Embankment Pond Issues

## Other Issues

| Problem   | MWO                      |
|---|--------------------------|
| 6' Fence and Barbed Wire at Fence, could not access into pond area. | <input type="checkbox"/> |

# POND REPORT

**Facility No** 201      **County** Queen Anne's      **District**  
**Inspection Date** 31-Mar-10      **Inspection Time** 2:20:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Northbrook Subdivision Lurgan Stand Edenderry Ave

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment    |
|-------------------------------------|------------|
| <input checked="" type="checkbox"/> | Very minor |

### Trash Issues

| Trash Present                       | Comment    |
|-------------------------------------|------------|
| <input checked="" type="checkbox"/> | Very minor |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Within Pond      | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 202      **County**      **District**  
**Inspection Date** 31-Mar-10      **Inspection Time** 1:01:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Northbrook Subdivision, Lurgen and Granard Avenue

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

| Trash Present                       | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Other          | Within Pond      | <input type="checkbox"/> | Cattail |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Within Pond      | <input type="checkbox"/> |         |
| Trees          | Surrounding Pond | <input type="checkbox"/> |         |
| Trees          | Within Pond      | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 241      **County**      **District**  
**Inspection Date** 06-May-10    **Inspection Time** 9:35:00 AM    **Overall Condition**  
**Pond Type** Dry Pond    **Embankment Pond**     **As-Built Available**   
**BMP Location** Inter of Rt 213 and Rt 18

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Outlet Channel        | Good      | <input type="checkbox"/> |
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

**Trash Issues**  
**Trash Present**     **Comment**

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 308      **County** Queen Anne's      **District**  
**Inspection Date** 06-May-10      **Inspection Time** 1:15:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**

**BMP Location** At End of Circle on Comet Drive, Rear of Building 152

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

| Inadequate Cover         | Location |
|--------------------------|----------|
| <input type="checkbox"/> |          |

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment    |
|----------------|------------------|--------------------------|------------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |            |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> | Very Minor |
| Phragmites     | Within Pond      | <input type="checkbox"/> |            |
| Trees          | Within Pond      | <input type="checkbox"/> | Minor      |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 321      **County** Queen Anne's      **District**  
**Inspection Date** 14-May-10      **Inspection Time** 9:50:00 AM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Symphony Village, Near Sonata Way & Symphony Way

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

| Trash Present                       | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> |         |

### Unwanted\_Vegetation Issues

| Type       | Location         | MWO                      | Comment   |
|------------|------------------|--------------------------|---|
| Phragmites | Surrounding Pond | <input type="checkbox"/> | Large amount of vegetation at discharge pipe (c |

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 322      **County**      **District**  
**Inspection Date** 04-May-10    **Inspection Time** 10:45:00 AM    **Overall Condition**  
**Pond Type** Wet Pond    **Embankment Pond**     **As-Built Available**   
**BMP Location** Symphony Village, Near Overture Way & Encore Ct

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Forebay                      | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Good      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 334      **County**      **District**  
**Inspection Date** 31-Mar-10    **Inspection Time** 10:45:00 AM    **Overall Condition**  
**Pond Type** Wet Pond    **Embankment Pond**     **As-Built Available**   
**BMP Location** Northbrook Subdivision (Northbrook Drive & Long Creek Way)

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type       | Location         | MWO                      | Comment |
|------------|------------------|--------------------------|---------|
| Phragmites | Surrounding Pond | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues



# POND REPORT

**Facility No** 335      **County**      **District**  
**Inspection Date** 31-Mar-10    **Inspection Time** 11:30:00 AM    **Overall Condition**  
**Pond Type** Wet Pond    **Embankment Pond**     **As-Built Available**

**BMP Location** Northbrook Subdivision (South end of Northbrook Drive between Circles)

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Poor      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment    |
|-------------------------------------|------------|
| <input checked="" type="checkbox"/> | Very Minor |

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 337      **County** Queen Anne's      **District**  
**Inspection Date** 04-May-10      **Inspection Time** 11:35:00 AM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**

**BMP Location** Symphony Village, Near Taylor Mill Rd. & Bravo Rd, off Harmony Way

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Access Road                 | Good      | <input type="checkbox"/> |
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### RipRap Issues

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment   |
|----------------|------------------|--------------------------|---|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |   |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> | Canada Thistle on surrounding west side near In |
| Phragmites     | Within Pond      | <input type="checkbox"/> | Phragmites surround both bottom of pond and s   |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 369      **County** Queen Anne's      **District**  
**Inspection Date** 12-May-10      **Inspection Time** 10:30:00 AM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Centreville United Methodist Church, 608 Church Hill Road

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Emergency Spillway    | Good      | <input type="checkbox"/> |
| Outlet Channel        | Good      | <input type="checkbox"/> |
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment  |
|----------------|------------------|--------------------------|----------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |          |
| Other          | Surrounding Pond | <input type="checkbox"/> | Cattails |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |          |
| Phragmites     | Within Pond      | <input type="checkbox"/> |          |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 387      **County** Queen Anne's      **District**  
**Inspection Date** 13-May-10      **Inspection Time** 11:10:00 AM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Side of Crossroad Community Center, Off Banjo Lane

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Plastic  | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present           | Comment |
|--------------------------|---------|
| <input type="checkbox"/> |         |

### Trash Issues

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

| Problem        | MWO                                 |
|----------------|-------------------------------------|
| Animal Burrows | <input checked="" type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 388      **County**      **District**  
**Inspection Date** 04-May-10    **Inspection Time** 2:00:00 PM    **Overall Condition**  
**Pond Type** Dry Pond    **Embankment Pond**     **As-Builts Available**   
**BMP Location** Centreville Diagnostic Center, 2540 on Rt 213

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Emergency Spillway    | Good      | <input type="checkbox"/> |
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component              | Condition | MWO                      |
|------------------------|-----------|--------------------------|
| Pond Bottom            | Good      | <input type="checkbox"/> |
| Side Slope and Buffers | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Within Pond      | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 389      **County** Queen Anne's      **District**  
**Inspection Date** 06-May-10      **Inspection Time** 2:10:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Side of 408 S. Liberty St, and side of Millstream Park

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Side Slope and Buffer | Good      | <input type="checkbox"/> |
| Top of Slope          | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component              | Condition | MWO                      |
|------------------------|-----------|--------------------------|
| Pond Bottom            | Fair      | <input type="checkbox"/> |
| Side Slope and Buffers | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment              |
|-------------------------------------|----------------------|
| <input checked="" type="checkbox"/> | Minor debris in pond |

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment                                      |
|----------------|------------------|--------------------------|--|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> | (Minor)                                      |
| Trees          | Surrounding Pond | <input type="checkbox"/> | Surrounding Pond has Large Amounts of Trees, |
| Trees          | Within Pond      | <input type="checkbox"/> |  |

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

| Problem   | MWO                      |
|---|--------------------------|
| Good - based on exterior observation, interior of pond unaccessible due to trees, vegetation and fence. | <input type="checkbox"/> |

# POND REPORT

**Facility No** 405      **County**      **District**  
**Inspection Date** 04-May-10    **Inspection Time** 2:45:00 PM    **Overall Condition**  
**Pond Type** Wet Pond    **Embankment Pond**     **As-Built Available**   
**BMP Location** Rear of G&G Distributors (213) Pond Off Rt. 18

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

| Problem                         | MWO                      |
|---------------------------------|--------------------------|
| Sinkhole & Erosion Around Riser | <input type="checkbox"/> |

# POND REPORT

**Facility No** 42      **County** Queen Anne's      **District**  
**Inspection Date** 13-May-10      **Inspection Time** 1:35:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Side of Kennard School, Providence Farm on Little Kidwell Ave

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Trash Issues

| Trash Present                       | Comment                        |
|-------------------------------------|--------------------------------|
| <input checked="" type="checkbox"/> | Minor - From School and Develo |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment                         |
|----------------|------------------|--------------------------|---------------------------------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |                                 |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails                        |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |                                 |
| Phragmites     | Within Pond      | <input type="checkbox"/> | Large amount within pond bottom |

### Bike Trails and Animal Burrows

| Problem        | MWO                                 |
|----------------|-------------------------------------|
| Animal Burrows | <input checked="" type="checkbox"/> |

### Embankment Pond Issues

### Other Issues



# POND REPORT

**Facility No** 422      **County** Queen Anne's      **District**  
**Inspection Date** 31-Mar-10      **Inspection Time** 8:50:00 AM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Northbrook Subdivision (MD 213/Wexford Drive)

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Other          | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

| Inadequate Cover         | Location |
|--------------------------|----------|
| <input type="checkbox"/> |          |

### Debris Issues

| Debris Present                      | Comment                |
|-------------------------------------|------------------------|
| <input checked="" type="checkbox"/> | minor from development |
| <input type="checkbox"/>            |                        |

### Trash Issues

| Trash Present                       | Comment                |
|-------------------------------------|------------------------|
| <input checked="" type="checkbox"/> | Minor from development |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 423      **County**      **District**  
**Inspection Date** 31-Mar-10      **Inspection Time** 2:55:00 PM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Northbrook Subdivision (Wexford Drive & Trickling Brook)

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Debris Issues

### Unwanted\_Vegetation Issues

### Bike Trails and Animal Burrows

### Other Issues

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Trash Issues

### Embankment Pond Issues

# POND REPORT

**Facility No** 424      **County**      **District**  
**Inspection Date** 31-Mar-10      **Inspection Time** 9:53:00 AM      **Overall Condition**  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Northbrook Subdivision (MD213) Brookfiel Dr & Northbrook Dr

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

| Component      | Condition | MWO                      |
|----------------|-----------|--------------------------|
| Inlet Channel  | Good      | <input type="checkbox"/> |
| Outlet Channel | Good      | <input type="checkbox"/> |

### Riser and Trash Rack Issues

| Material | Problem           | Debris on trash rack     |
|----------|-------------------|--------------------------|
| Concrete | Exposed Reinforce | <input type="checkbox"/> |
| Concrete | Spalling          | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem       | Joint Problem            | MWO                      |
|----------|---------------|--------------------------|--------------------------|
| Concrete | Exposed Reinf | <input type="checkbox"/> | <input type="checkbox"/> |
| Concrete | Spalling      | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Trash Issues

| Trash Present                       | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 449      **County** Queen Anne's      **District**  
**Inspection Date** 13-May-10      **Inspection Time** 2:40:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Rear of 2601 (Rt 213) Centreville Rd (cvach Financial)

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay                       | Good      | <input type="checkbox"/> |
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment |
|-------------------------------------|---------|
| <input checked="" type="checkbox"/> | Minor   |

### Trash Issues

| Trash Present                       | Comment       |
|-------------------------------------|---------------|
| <input checked="" type="checkbox"/> | minor amounts |
| <input type="checkbox"/>            | Minor         |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment |
|----------------|------------------|--------------------------|---------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |         |
| Phragmites     | Within Pond      | <input type="checkbox"/> |         |

### Bike Trails and Animal Burrows

### Embankment Pond Issues

| Problem                    | Condition | MWO                      |
|----------------------------|-----------|--------------------------|
| Local Depression or Bulges | Good      | <input type="checkbox"/> |

### Other Issues

| Problem  | MWO                      |
|--|--------------------------|
| Some Minor Erosion on North and South Side of Pond | <input type="checkbox"/> |

# POND REPORT

---

**Facility No** 51      **County** Queen Anne's      **District**  
**Inspection Date** 10-May-10      **Inspection Time** 1:10:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** Intersection of Johnstown Ln and Powell, Rear of Queen Annes County Senior Center  
**Setting**

---

## Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

## Sedimentation Issues

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Good      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

## RipRap Issues

## Riser and Trash Rack Issues

## Principal Spillway Barrel Issues

## Inadequate Vegetative Cover Issues

## Debris Issues

## Trash Issues

## Unwanted\_Vegetation Issues

## Bike Trails and Animal Burrows

## Embankment Pond Issues

## Other Issues

# POND REPORT

**Facility No** 52      **County** Queen Anne's      **District**  
**Inspection Date** 12-May-10      **Inspection Time** 2:47:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**

**BMP Location** Rear of Queen Annes County detention Center on Little Hut Lane

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Inlet Structures or Channels  | Good      | <input type="checkbox"/> |
| Outlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                   | Good      | <input type="checkbox"/> |
| Side Slope and Buffers        | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

### Principal Spillway Barrel Issues

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present           | Comment |
|--------------------------|---------|
| <input type="checkbox"/> | Minor   |

### Trash Issues

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment              |
|----------------|------------------|--------------------------|----------------------|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> |                      |
| Other          | Within Pond      | <input type="checkbox"/> | Cattails             |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |                      |
| Phragmites     | Within Pond      | <input type="checkbox"/> | Large amount in Pond |

### Bike Trails and Animal Burrows

### Embankment Pond Issues

### Other Issues

# POND REPORT

**Facility No** 81      **County**      **District**  
**Inspection Date** 06-May-10    **Inspection Time** 10:18:00 AM    **Overall Condition**  
**Pond Type** Wet Pond    **Embankment Pond**     **As-Builts Available**

**BMP Location** At Weatherbee Subdivision on Frederick Drive, Rear side of G&G Distributors

**Setting**

**Erosion Issues**

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Fair      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

**Sedimentation Issues**

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Fair      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

**RipRap Issues**

**Riser and Trash Rack Issues**

**Principal Spillway Barrel Issues**

**Inadequate Vegetative Cover Issues**

**Debris Issues**

| Debris Present                      | Comment               |
|-------------------------------------|-----------------------|
| <input checked="" type="checkbox"/> | Some Minor - Moderate |

**Trash Issues**

**Unwanted\_Vegetation Issues**

| Type           | Location         | MWO                                 | Comment  |
|----------------|------------------|-------------------------------------|--|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/>            |  |
| Phragmites     | Surrounding Pond | <input checked="" type="checkbox"/> |  |
| Trees          | Surrounding Pond | <input checked="" type="checkbox"/> | Surrounding Pond has large amounts of trees an |

**Bike Trails and Animal Burrows**

**Embankment Pond Issues**

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

**Other Issues**

| Problem  | MWO                      |
|--|--------------------------|
| Fair - based on exterior observations of pond, some parts of pond unaccessible to get to | <input type="checkbox"/> |

# POND REPORT

---

**Facility No** 83      **County** Queen Anne's      **District**  
**Inspection Date** 12-May-10      **Inspection Time** 11:35:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Built Available**   
**BMP Location** Side of Acme in Centreville Plaza, off Little Hut Lane  
**Setting**

---

## Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

## Sedimentation Issues

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Good      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

## RipRap Issues

## Riser and Trash Rack Issues

## Principal Spillway Barrel Issues

## Inadequate Vegetative Cover Issues

## Debris Issues

## Trash Issues

## Unwanted\_Vegetation Issues

## Bike Trails and Animal Burrows

## Embankment Pond Issues

## Other Issues



# POND REPORT

**Facility No** 99      **County** Queen Anne's      **District**  
**Inspection Date** 11-May-10      **Inspection Time** 2:50:00 PM      **Overall Condition** Good  
**Pond Type** Wet Pond      **Embankment Pond**       **As-Builts Available**   
**BMP Location** 160 Cypress Court, Rear of, in Circle

## Setting

### Erosion Issues

| Component                   | Condition | MWO                      |
|-----------------------------|-----------|--------------------------|
| Emergency Spillway          | Good      | <input type="checkbox"/> |
| Inlet Structure or Channels | Good      | <input type="checkbox"/> |
| Outlet Channel              | Good      | <input type="checkbox"/> |
| Side Slope and Buffer       | Good      | <input type="checkbox"/> |
| Top of Slope                | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                    | Condition | MWO                      |
|------------------------------|-----------|--------------------------|
| Inlet Structures or Channels | Good      | <input type="checkbox"/> |
| Pond Bottom                  | Good      | <input type="checkbox"/> |
| Side Slope and Buffers       | Good      | <input type="checkbox"/> |

### RipRap Issues

### Riser and Trash Rack Issues

| Material | Problem | Debris on trash rack     |
|----------|---------|--------------------------|
| Concrete | None    | <input type="checkbox"/> |

### Principal Spillway Barrel Issues

| Material | Problem | Joint Problem            | MWO                      |
|----------|---------|--------------------------|--------------------------|
| Concrete | None    | <input type="checkbox"/> | <input type="checkbox"/> |

### Inadequate Vegetative Cover Issues

### Debris Issues

| Debris Present                      | Comment              |
|-------------------------------------|----------------------|
| <input checked="" type="checkbox"/> | Minor amount in Pond |

### Trash Issues

| Trash Present                       | Comment                       |
|-------------------------------------|-------------------------------|
| <input checked="" type="checkbox"/> | Very minor amount from Develo |

### Unwanted\_Vegetation Issues

| Type           | Location         | MWO                      | Comment  |
|----------------|------------------|--------------------------|--|
| Canada Thistle | Surrounding Pond | <input type="checkbox"/> | Large amount of Vegetation, Brush and Trees ar |
| Phragmites     | Surrounding Pond | <input type="checkbox"/> |  |
| Phragmites     | Within Pond      | <input type="checkbox"/> |  |
| Trees          | Surrounding Pond | <input type="checkbox"/> |  |
| Trees          | Within Pond      | <input type="checkbox"/> |  |

### Bike Trails and Animal Burrows

| Problem        | MWO                      |
|----------------|--------------------------|
| Animal Burrows | <input type="checkbox"/> |

### Embankment Pond Issues

### Other Issues

the 1990s, the number of people in the UK who are aged 65 and over has increased from 10.5 million to 13.5 million (1990-2000) (ONS 2001).

There is a growing awareness of the need to address the needs of older people in the workplace. The Department of Health (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

The Department of Work and Pensions (2000) has highlighted the need to address the needs of older people in the workplace, and the Department of Health (2000) has highlighted the need to address the needs of older people in the workplace.

# INFILTRATION FACILITY REPORT

**Facility No** 12      **County** Queen Anne's  
**Inspection Date** 12-May-10      **Inspection Time** 1:15:00 PM      **Overall Condition** Good  
**BMP Type** Infiltration Basin / Trench      **Embankment Pond**       **As-Built Available**   
**BMP Location** Center Park Apt., Behind Railroad Ave, off Little Hut Lane  
**Setting**

| <b>Erosion Issues</b> |                  |                          | <b>Sedimentation Issues</b> |                  |                          |
|-----------------------|------------------|--------------------------|-----------------------------|------------------|--------------------------|
| <b>Component</b>      | <b>Condition</b> | <b>MWO</b>               | <b>Component</b>            | <b>Condition</b> | <b>MWO</b>               |
| Trench Basin Area     | Good             | <input type="checkbox"/> | Trench/Basin Area           | Good             | <input type="checkbox"/> |
| Upland drainage basin | Good             | <input type="checkbox"/> |                             |                  |                          |

**Debris Issues**

**Trash Issues**

**Unwanted\_Vegetation Issues**

**Seeding Required**

**Mowing Issues**

**Pretreatment Area**

**Aggregate**  
**Surface of Aggregate Clean**       **Stone replacement needed**       **MWO**

**BMP Outlet**

**Ponding**

# INFILTRATION FACILITY REPORT

---

**Facility No** 124      **County** Queen Anne's

**Inspection Date** 10-May-10      **Inspection Time** 2:05:00 PM      **Overall Condition** Good

**BMP Type** Infiltration Basin / Trench      **Embankment Pond**       **As-Built Available**

**BMP Location** End of Armstrong Drive, Front of Corsica Hills Long Term Care and Rehab

## Setting

---

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component         | Condition | MWO                      |
|-------------------|-----------|--------------------------|
| Trench/Basin Area | Good      | <input type="checkbox"/> |

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

### Seeding Required

### Mowing Issues

### Pretreatment Area

### Aggregate

### BMP Outlet

| Outlet Material | Condition |
|-----------------|-----------|
| RipRap          |           |

### Ponding

# INFILTRATION FACILITY REPORT

Facility No 183 County Queen Anne's

Inspection Date 11-May-10 Inspection Time 1:15:00 PM Overall Condition Good

BMP Type Infiltration Basin / Trench Embankment Pond  As-Built Available

BMP Location 335 N. Liberty St (Rt 213) Across from Centreville Police Dept.

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| BMP Outlet            | Good      | <input type="checkbox"/> |
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component                     | Condition | MWO                      |
|-------------------------------|-----------|--------------------------|
| Forebay/Pretreatment Inlet Ar | Good      | <input type="checkbox"/> |
| Forebay/Pretreatment Inlet Pi | Good      | <input type="checkbox"/> |
| Trench/Basin Area             | Good      | <input type="checkbox"/> |

### Debris Issues

### Trash Issues

### Unwanted\_Vegetation Issues

| Type       | Location         | MWO                      | Comment |
|------------|------------------|--------------------------|---------|
| Phragmites | Surrounding Pond | <input type="checkbox"/> |         |

### Seeding Required

### Mowing Issues

### Pretreatment Area

### Aggregate

### BMP Outlet

| Outlet Material | Condition |
|-----------------|-----------|
| Riprap          |           |

### Ponding

# INFILTRATION FACILITY REPORT

**Facility No** 25      **County** Queen Anne's  
**Inspection Date** 10-May-10    **Inspection Time** 2:40:00 PM    **Overall Condition** Good  
**BMP Type** Infiltration Basin / Trench    **Embankment Pond**     **As-Builts Available**   
**BMP Location** Armstrong Ave., Rear of Corsica Hill Long Term Care and Rehab  
**Setting**

## Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| BMP Outlet            | Good      | <input type="checkbox"/> |
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

## Sedimentation Issues

| Component         | Condition | MWO                      |
|-------------------|-----------|--------------------------|
| Trench/Basin Area | Good      | <input type="checkbox"/> |

## Debris Issues

## Trash Issues

## Unwanted\_Vegetation Issues

## Seeding Required

## Mowing Issues

## Pretreatment Area

## Aggregate

## BMP Outlet

| Outlet Material | Condition |
|-----------------|-----------|
| RipRap          |           |

## Ponding

# INFILTRATION FACILITY REPORT

---

**Facility No** 257      **County** Queen Anne's  
**Inspection Date** 11-May-10    **Inspection Time** 2:15:00 PM    **Overall Condition** Good  
**BMP Type** Infiltration Basin / Trench    **Embankment Pond**     **As-Built Available**   
**BMP Location** Side of 202 Ridgeview Court, at Townhomes, Side of  
**Setting** This appears to be a Storm Well per JK ON 5/11/10

---

**Erosion Issues**

**Sedimentation Issues**

**Debris Issues**

**Trash Issues**

**Unwanted\_Vegetation Issues**

**Seeding Required**

**Mowing Issues**

**Pretreatment Area**

**Aggregate**

**BMP Outlet**

**Ponding**

# INFILTRATION FACILITY REPORT

**Facility No** 27      **County** Queen Anne's

**Inspection Date** 10-May-10      **Inspection Time** 11:20:00 AM      **Overall Condition** Good

**BMP Type** Infiltration Basin / Trench      **Embankment Pond**       **As-Built Available**

**BMP Location** Rear of Delmarva Power and Light on Rt 213, 2600 Centreville Road

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component         | Condition | MWO                      |
|-------------------|-----------|--------------------------|
| Trench/Basin Area | Good      | <input type="checkbox"/> |

### Debris Issues

### Trash Issues

| Trash Present            | Comment           |
|--------------------------|-------------------|
| <input type="checkbox"/> | very minor debris |

### Unwanted\_Vegetation Issues

### Seeding Required

### Mowing Issues

### Pretreatment Area

### Aggregate

| Surface of Aggregate Clean | Stone replacement needed | MWO                      |
|----------------------------|--------------------------|--------------------------|
| <input type="checkbox"/>   | <input type="checkbox"/> | <input type="checkbox"/> |

### BMP Outlet

### Ponding



# INFILTRATION FACILITY REPORT

Facility No 3 County Queen Anne's

Inspection Date 13-May-10 Inspection Time 9:40:00 AM Overall Condition

BMP Type Infiltration Basin / Trench Embankment Pond  As-Built Available

BMP Location 505 Railroad Ave, Side of Police / Sheriffs Dept

## Setting

### Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| BMP Outlet            | Good      | <input type="checkbox"/> |
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

### Sedimentation Issues

| Component         | Condition | MWO                      |
|-------------------|-----------|--------------------------|
| Trench/Basin Area | Good      | <input type="checkbox"/> |

### Debris Issues

| Debris Present           | Comment |
|--------------------------|---------|
| <input type="checkbox"/> |         |

### Trash Issues

| Trash Present            | Comment |
|--------------------------|---------|
| <input type="checkbox"/> |         |

### Unwanted\_Vegetation Issues

### Seeding Required

### Mowing Issues

### Pretreatment Area

### Aggregate

### BMP Outlet

### Ponding

# INFILTRATION FACILITY REPORT

Facility No Temp 500 County Queen Anne's

Inspection Date 13-May-10 Inspection Time 12:20:00 PM Overall Condition Good

BMP Type Rain Garden Embankment Pond  As-Built Available

BMP Location Queen Annes County Free Library, on Rt 213 (S. Commerce St) Rear of  
Setting

## Erosion Issues

| Component             | Condition | MWO                      |
|-----------------------|-----------|--------------------------|
| BMP Outlet            | Good      | <input type="checkbox"/> |
| Trench Basin Area     | Good      | <input type="checkbox"/> |
| Upland drainage basin | Good      | <input type="checkbox"/> |

## Sedimentation Issues

| Component         | Condition | MWO                      |
|-------------------|-----------|--------------------------|
| Trench/Basin Area | Good      | <input type="checkbox"/> |

## Debris Issues

## Trash Issues

| Trash Present                       | Comment      |
|-------------------------------------|--------------|
| <input checked="" type="checkbox"/> | Minor litter |

## Unwanted\_Vegetation Issues

## Seeding Required

## Mowing Issues

## Pretreatment Area

## Aggregate

## BMP Outlet

| Outlet Material | Condition |
|-----------------|-----------|
| RipRap          |           |

## Ponding

# **ATTACHMENT 2**